



US Army Corps
of Engineers
Waterways Experiment
Station


Technical Report HL-94-14
September 1994

AD-A285 544



Claremont Terminal Channel, New York Harbor

by Randy A. McCollum, Barbara P. Donnell



Approved For Public Release; Distribution Is Unlimited

9410

94-32075



1478

DTIC

Claremont Terminal Channel, New York Harbor

by Randy A. McCollum, Barbara P. Donnell

U.S. Army Corps of Engineers
Waterways Experiment Station
3909 Halls Ferry Road
Vicksburg, MS 39180-6199


Accession For	
NTIS	CRA&I <input checked="" type="checkbox"/>
DTIC	TAB <input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution /	
Availability Codes	
Dist	Avail and/or Special
A-1	

Final report

Approved for public release; distribution is unlimited



**US Army Corps
of Engineers**
Waterways Experiment
Station



Waterways Experiment Station Cataloging-in-Publication Data

McCollum, Randy A.

Claremont Terminal Channel, New York Harbor / by Randy A.
McCollum, Barbara P. Donnell ; prepared for U.S. Army Engineer Dis-
trict, New York.

145 p. : ill. ; 28 cm. — (Technical report ; HL-94-14)

Includes bibliographic references.

1. Navigation — Atlantic Coast (N.J.) — Simulation methods. 2. Channels
(Hydraulic engineering) — New Jersey — Jersey City — Design and con-
struction — Evaluation. 3. Claremont Terminal Channel (N.J.) — Design
and construction — Evaluation. 4. Harbors — New York (N.Y.) — Hydro-
dynamics — Computer simulation. I. Donnell, Barbara P. II. United
States. Army. Corps of Engineers. New York District. III. U.S. Army Engi-
neer Waterways Experiment Station. IV. Hydraulics Laboratory (U.S.)
V. Title. VI. Series: Technical report (U.S. Army Engineer Waterways Ex-
periment Station) ; HL-94-14.

TA7 W34 no.HL-94-14

Contents

Preface	v
Conversion Factors, Non-SI to SI Units of Measurement	vi
1—Introduction	1
Proposed Channel Improvements	1
Purpose and Scope of Investigation	2
2—Data Development	3
Channel	3
Visual Scene	4
Radar	5
Current	5
Test Ship	5
Wind	6
Tug Boats	6
3—Navigation Study	7
Validation	7
Test Conditions	9
4—Study Results	12
Pilot Evaluations	12
Inbound, flood tide	12
Inbound, ebb tide	13
Outbound, flood tide	13
Outbound, ebb tide	13
Summary	14
Final Questionnaires	14
Navigation Parameter Plots	17
Ship speed and engine RPM	18
Minimum clearance distances and rudder position	20
Summary	23
Ship Track Plots	23
Inbound, flood tide	23
Inbound, ebb tide	25

Outbound, flood tide	26
Outbound, ebb tide	27
5—Conclusions and Recommendations	29
Limitations of the Study	29
Conclusions	30
Recommendations	32
Appendix A: Claremont Channel Ship Simulator	
Hydrodynamic Study	A1
Introduction	A1
Background	A1
Objective	A4
Scope	A4
Technical Approach	A4
Hydrodynamic Numerical Modeling	A5
The TABS-MD Modeling System	A5
Computational Environment	A5
The Computational Meshes	A5
Hydrodynamic Validation	A9
Test of Base Versus Plan Channel Designs	A25
Procedures	A25
Hydrodynamic Comparisons	A25
Summary and Conclusions	A36
Appendix B: The TABS-MD System	B1
Finite Element Modeling	B3
The Hydrodynamic Model, RMA2	B3
The Sediment Transport Model, STUDH	B7
The Water Quality Transport Model, RMA4	B14
References	B17

SF 298

Preface

The ship simulator investigation and numerical modeling of hydrodynamic conditions for the Claremont Channel, New York Harbor, New York, Project, as documented in this report were performed for the U.S. Army Engineer District, New York (CENAN).

Mr. Frank Santangelo was the CENAN-PL-CE liaison during the study.

The ship simulator investigation was conducted in the Hydraulics Laboratory (HL) of the U.S. Army Engineer Waterways Experiment Station (WES) from October 1992 to March 1993 under the direction of Messrs. Frank A. Herrmann, Jr., Director, HL; Richard A. Sager, Assistant Director, HL; M. B. Boyd, Chief, Waterways Division (HR) (retired); and Dr. L. L. Daggett, Chief, Navigation Branch (HRN). The study was performed and the report prepared by Mr. R. A. McCollum, Navigation Branch. Ms. D. C. Derrick (HRN) provided assistance in preparation of the visual scene database.

The hydrodynamic model study was conducted in the HL, WES, from June 1992 to May 1993 under the direction of Messrs. Herrmann, Sager, William H. McAnally, Jr., Chief, Estuaries Division (ED), and David R. Richards, Chief, Estuarine Simulation Branch (ESB), ED. The work was performed and the report was prepared by Ms. Barbara Park Donnell, ESB. Mr. Joseph V. Letter, Jr., ED, provided insights pertaining to previous numerical modeling work in New York Harbor. Mr. Ben Brown, Jr., ESB, served as the primary assistant for the mesh development.

At the time of publication of this report, Director of WES was Dr. Robert W. Whalin. Commander was COL Bruce K. Howard, EN.

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products.

Conversion Factors, Non-SI to SI Units of Measurement

Non-SI units of measurement used in this report can be converted to SI units as follows:

Multiply	By	To Obtain
cubic feet	0.02831685	cubic meters
cubic feet per second	0.02831685	cubic meters per second
feet	0.3048	meters
feet per second	0.3048	meters per second

1 Introduction

Claremont Terminal Channel is located on the eastern shoreline of the Upper Bay of New York Harbor at Jersey City, New Jersey (Plate 1). The existing deep-water channel varies in available width at a depth of from 25 to 27 ft with a minimum width of approximately 150 ft in some locations from the Claremont Terminal to the intersection with the federally maintained Anchorage Channel.

The typical ship using the port is a Panamax bulk carrier with lengths as great as 760 ft, beam of 106 ft, typically drafting 16 ft at the bow, 20 ft at the stern in ballast and 30 ft, even keel, loaded. The typical operation is to come into the port in ballast, turning off the end of the Caven Point (or sometimes referred to as Ocean Terminal) Pier, in the intersections of the Claremont and Pierhead Channels, with the assistance of two tugs, rated between 3000 and 4000 hp, and back into the dock. The ship is loaded to draft 30 ft, then the pilot waits for maximum flood tide (the tidal range is 4.7 ft above mean low water, mlw) to make their transit out. This allows from less than 1 ft to 1.5 ft underkeel clearance. The export material is mainly scrap metal.

The design draft of the vessel type used in this port is 41 ft. Vessels are normally loaded to 36 ft before leaving for their destinations. Due to the channel depth restriction, the vessels loaded at Claremont are loaded only to 30 ft, then required to go to another port to "top off".

Proposed Channel Improvements

The proposed channel improvements are for the deep-water channel to become a federally maintained channel, deepened to 34-ft mlw and widened to 300 ft. The entrance transition width from the Anchorage Channel is designed to be 1,250 ft with both north and south transitions tapering to the 300-ft Claremont Channel width. The plan proposes to require ships to turn in the Anchorage Channel and back into the Claremont Channel. This requires that tugs of adequate capacity to handle the ballasted design ship in maximum ebb and flood tide currents be available.

Purpose and Scope of Investigation

The purpose of the ship simulator investigation is to develop a safe and optimal navigation channel, including a ship turning area which will accommodate the design vessel. This is accomplished by testing with the existing condition along with proposed channel improvements to determine the relative difficulty and safety of operation for each condition.

The study limits of the Claremont Terminal Channel simulation were from the Claremont Terminal to the intersection with the Anchorage Channel, then approximately 2 miles of the Anchorage Channel south of the intersection with the Claremont Channel (Plate 1). Approximately 1,000 ft of the Anchorage Channel north of the intersection with the Claremont Channel was modeled to allow for turning maneuvers. The plans tested were:

- a. Existing Condition (Plate 2)
- b. 300 ft by 34 ft, Plan A proposed in the Feasibility Report (Plate 3)
- c. 300 ft by 34 ft from Anchorage Channel to Ocean Terminal Pier, 250 ft by 34 ft from Ocean Terminal Pier to Claremont Terminal, Plan B (Plate 4)

Turning maneuvers will be tested off the end of the Ocean Terminal Pier for Plan A and in the Anchorage Channel for Plan B since the plans are identical from the Anchorage Channel up to the end of the pier.

2 Data Development

In order to properly simulate the study area, it is necessary to develop information relative to five types of input data:

- a. Channel data base contains dimensions for the existing channel and the proposed channel modifications. It includes the channel cross-sections, bank slope angle, overbank depth, initial conditions, and autopilot track-line and speed definition.
- b. Visual scene data base is composed of three-dimensional images of principal features of the simulated area, including the aids to navigation, docks, and buildings.
- c. Radar data base contains the features for the plan view of the study area.
- d. Ship data file contains characteristics and hydrodynamic coefficients for the test vessels.
- e. Current pattern data in the channel including the magnitude and direction of the current and the water depth for each cross section defined in the channel data base.

Channel

Channel cross sections are used to define the ship simulator channel data base. The information used to develop the channel data base came from the District-furnished hydrographic survey charts dated July 1992. This was the latest information available concerning depths, dimensions, and bank lines of the existing channel. State planar coordinates as shown on the hydrographic survey were used for the definition of the data bases. Prototype survey ranges were generally used to locate the simulator cross sections. If the prototype survey ranges were not spaced close enough or were not sufficiently oriented, a new range was interpolated.

The ship simulator model uses eight equally spaced points to define each cross section. At each of these points, a depth, current magnitude, and

direction are required. For each cross section, the width, right and left bank slopes, and overbank depths are required. The channel depth, current magnitude, and direction for each of the eight points was provided by a TABS-2 model (Appendix A).

The channel side slope and overbank depth are used to calculate bank effects on the passing test vessel. The shallower the overbank and the steeper the side slope, the greater the computed bank effects. A small difference (1 to 2 ft) in channel and overbank depth produces negligible bank forces and moments.

Visual Scene

The visual scene data was created using information obtained from the National Oceanic and Atmospheric Administration (NOAA) chart number 12334, dated December 1984, the 1992 hydrographic survey, and photographs of the area. As in the development of the channel data base, the state planar coordinate system was used. Comments by local pilots and Corps of Engineer personnel constituted other sources of information for the scene. These allowed inclusion of the significant features and also helped determine which, if any, features the pilots use for informal ranges and location sightings. All aids-to-navigation such as buoys, buildings, docks, towers, and tanks were included in the visual scene.

The visual scene is generated in three dimensions: north-south, east-west, and vertical elevation. As the ship progresses through the channel, the three-dimensional picture is constantly transformed into a two-dimensional perspective graphic image representing the relative size of the objects in the scene as a function of the vessel's position and orientation and the relative direction and position on the ship bridge for viewing. The graphics hardware used for this project was a stand-alone computer (Silicon Graphics-Iris 4D/35). This computer performs all the visual scene generation as well as the hydrodynamic interactions of ship, current, wind, and pilot command. Information which includes parameters such as vessel heading, rate of turn, forward and lateral velocity, and position are displayed on the precision navigation parameter screen. The field of view is approximately 40 degrees. The viewing angle, which normally is straight ahead, can be changed to any angle by a look-around feature. This feature simulates the pilot's ability to see any object with a turn of his head. The pilot's position on the bridge can also be changed from the center of the bridge to any position wing to wing to simulate the pilot walking across the bridge to obtain a better view, e.g., along the edge of the ship from the bridge wing.

Radar

The radar data base is used by the radar software to create a simulated radar for use by the test pilots. The radar data base contains X- and Y-coordinates that define the border between land and water. The file also contains coordinates for any structure on the bank or extending into the water such as bridges, docks, piers, and aids to navigation. In short, these data basically define what a pilot would see on a shipboard radar. The radar image is a continuously updated plan view of the vessel's position relative to the surrounding area. Three different ranges of 0.5 mile, 0.75 mile, and 1.5 miles were programmed to enable the pilot to choose the scale needed.

Current

A current data base contains current magnitude, direction, and channel bottom depths at eight points across the channel at each of the cross sections defined in the channel. Interpolation of the data between cross sections provides continuous and smooth current patterns during testing.

Accurate simulation of ship handling in the Claremont and Anchorage Channels required detailed modeling of the currents in New York Harbor. A TABS-2 model study was performed to provide these currents (Appendix A). Current data bases were developed for the existing, Plan A, and Plan B channels. Verification of the currents for the existing channel was by comparison to physical model results. Maintained channel depths are referenced to mean low water for New York Harbor. Currents were provided for the maximum ebb and flood tides during spring tide where both the highest current magnitudes and maximum tide advantage was present. This was determined to be at 39.25 hours (flood tide) and 44.00 hours (ebb tide) during the tidal cycle used with the TABS model. Vector plots showing the magnitude and direction of the currents generated by the TABS model are shown in Plates 5-10. Currents for the simulator are interpolated from the current fields provided by the TABS model to eight points along each cross-section of the channels. Vector plots showing the magnitude and direction of the interpolated currents used for simulator testing are presented in Plates 11-16.

Test Ship

One design ship was used for pilot testing. The vessel required a ship data base consisting of the ship characteristics and coefficients used in the ship hydrodynamic model for calculating forces and moments acting upon the vessel.

The vessel used in the simulation was based on the design ship which is 760 ft long, has a 106-ft beam, 41-ft design draft and 50,000 DWT.

displacement. This vessel was to be tested in ballast with 16-ft draft at the bow and 20-ft draft at the stern, 30-ft even keel draft for the loaded, existing condition, and 36-ft even keel for the load plan conditions. The ship model was developed under a contract with DESIGN AND PLANNERS, INC., Arlington, VA. (report in preparation).

Wind

Based on conversations with local pilots, the prevalent wind direction was determined to be from the southwest. The highest sustained wind in which they would navigate the channel was determined to be about 25 miles per hour (mph). Winds coming from that direction and at the magnitude specified occur frequently. The simulator models wind as gusting plus or minus 70 percent about the specified 25-mph average. The direction of the wind also randomly varies, with southwest being the predominant direction. Wind effect was spatially uniform and was not diminished by natural windbreaks such as land topography or man-made objects, such as buildings or docks.

Tug Boats

Based on conversations with local pilots, two tug boats, each rated at 4000 hp were available to the pilot. The tugs could be placed on either side at the bow or stern and could be directed to either push or pull. Magnitudes of power could be entered in 25 percent increments from 0 to 100 percent. A radar image screen with a range of approximately .25 mile was used to indicate magnitude and direction of thrust. A vector from the bow or stern of the vessel indicated position and direction of thrust and the length indicated relative magnitude. As vessel speed increased, the length of the vector decreased as the tug effectiveness was reduced.

3 Navigation Study

Formal pilot testing was conducted with 6 pilots who were familiar with and licensed to operate in the Claremont Terminal Channel. Involving local professional pilots incorporated their experience and familiarity with handling ships in the study area into the navigation project evaluation. The tests were conducted using the WES ship simulator.

The WES ship simulator provides the pilot with a helm control, visual references, radar images, and precision navigation parameters such as heading, speed across the bottom, speed through the water, lateral speeds for the bow and stern, wind direction and magnitude, engine rpm setting, and rate of turn; these are information that he would normally have on the bridge of a ship. In this study, WES personnel served as helmsmen, manning the controls for ship rudder, engine, and tug boat operation, at the command of the pilot.

Validation

The simulation was validated over a 5-day period with the assistance of two pilots familiar with operation in the Claremont Channel. The following information was verified and fine tuned during validation:

- a. Ship models
- b. The channel definition.
 - (1) Bank conditions.
 - (2) Currents.
- c. Wind forces.
- d. The radar image and visual scene of the study area.
 - (1) Location of all aids to navigation.
 - (2) Land/water edge

(3) Landmarks such as buildings, loading facilities, etc.

To validate the ship models, the pilots were allowed to make both inbound and outbound runs with no wind or current effects, then asked to evaluate the reaction of the ship. The validation pilots both agreed that the ship was extremely sluggish in response to engine commands, did not back as strongly as they would expect, and did not twist (torque) as expected when backing. The engine response was improved so that engine rpm responded more quickly to engine command. The torquing expected during backing (the stern of the ship should move to the port, or left, during backing) was improved by increasing the torquing coefficients. The design of the ship model did not allow the engine to produce the same number of engine rpm astern as it does ahead, which the pilots said was normal in diesel-powered ships. To compensate for this, the WES helmsman ignored the one-quarter astern engine setting. When the pilot requested slow astern, one-half astern was used. For half-astern commands, three-quarters was used and any command above one-half got full astern. The pilots agreed that this yielded much better response. After the ship models were adjusted, the pilots were allowed to run with currents and winds to see if the ship still responded as they expected. The pilots both agreed that the ship model was still somewhat sluggish as compared to what they were familiar with, but not unreasonably so.

To validate the reaction of the vessel to bank forces, several simulation runs were made with the vessel transiting the entire study area. Special attention was given by the pilots to the response of the ship to the bank forces. If any problems were noted, the areas were isolated, and the prototype data for these areas was examined. The values for the overbank depth, the side slope, or the bank force coefficient would then be adjusted. Additional simulation runs would be undertaken through the problem areas, and if necessary, further adjustment was made. This process would be repeated until the pilot was satisfied that the simulated vessel response to the bank force was similar to that of an actual vessel passing through the same reach in the prototype. The pilots noted no problems with the bank forces and no adjustments were made.

The reaction of the vessel to current forces was verified by conducting several simulation runs over the entire study area without wind effect. The pilots were instructed to pay particular attention to current effects. The pilots were told that the model was set up to have the maximum ebb and flood tide currents that corresponded with the peak of tidal stage advantage. Both pilots agreed the currents were as strong as they would expect for such conditions and requested no changes.

To validate the wind effect on the vessel, the pilots were allowed to perform transits inbound and outbound with wind but no current effect, then asked to evaluate if the wind was affecting the ship as they would expect. The pilots both agreed the wind effect was as strong as they would expect and, if the wind were of any greater sustained magnitude, that they would not attempt to make passage through the Claremont Channel.

The pilots were allowed to make inbound and outbound runs with both the wind and current effect. The pilots stated that the greatest effect and highest difficulty would be when the wind and current were both moving in the same direction. The wind was initially set to come from the southwest. At the pilots' request, the wind was turned to come from the northeast with the ebb tide currents. The pilots agreed that the winds and currents were as strong as they expected and no further adjustments were made.

To validate the radar and visual scenes, the pilots were allowed to run through the channel and asked to point out anything in either the radar or visual image that needed to be added, deleted, or modified. The pilots asked that an apartment or condominium complex be added to the visual scene. A column of windows in this building complex is used as a range marker when coming into the Claremont Terminal. The pilots asked that a marker buoy near the end of the Ocean Terminal Pier be moved to the northwest to mark a shoal area. The pilots also asked that some of the moored barges be removed or relocated. One building was added approximately mid-length of the Ocean Terminal pier. It is used as a reference to mark a slight "dog-leg" in the existing channel.

The pilots also requested that the horsepower available for the tugs be reduced from 4,000 to 3,000. According to the pilots, tugs as large as 4,000 hp are not commonly available at this port, and 3,000-hp tugs are more typical of what would normally be available.

Test Conditions

The validation pilots stated that outbound traffic only went out with the peak flood tide in the existing channel. This is done to take advantage of the maximum tide differential of 4.5 ft so that the ships can be loaded as much as possible. Maximum ebb tide has 2.5-ft stage advantage over mean low water (mlw), so if the present channel is 25-27 ft below mlw, there is not enough depth to go out with a ship drafting 30 ft. Theoretically, Plan A and Plan B channels with a 34 ft depth below mlw would have opportunity to start outbound with peak ebb tide with a ship loaded to 36 ft since there would be a minimum of 36.5 ft of depth, providing approximately 0.5-ft underkeel, which is similar to the underkeel clearance for the existing channel with peak flood tide. Testing was conducted outbound with ebb tide for the plan channels to determine the viability of this procedure. For testing comparison of the existing condition versus the plan conditions, outbound tests with a ship drafting 30 feet was performed with ebb tide and the water depth available was adjusted to provide an underkeel clearance of about .5 feet, as does the Plan A and B channels. The environmental impact statement for Claremont, dated September 1986, states that the bottom of the channel has a layer of from 1 to 2 feet of soft silt. The validation pilots stated that at times, especially when the channel has silted in, that they "skim over" or "drive through" the soft bottom material, "feeling" their way through the channel.

The testing schedule as implemented on the WES ship simulator for the Claremont Terminal Channel is summarized in the following tabulation:

Plan	Direction	Tide	Ship Draft, ft	Channel Depth, ft	Tidal Stage, ft
Existing	Inbound	Flood	16,20	27	4.7
"	"	Ebb	"	27	2.5
"	Outbound	Flood	30	27	4.7
"	"	Ebb	"	28 ¹	2.5
Plan A	Inbound	Flood	16,20	34	4.7
"	"	Ebb	"	34	2.5
"	Outbound	Flood	36	34	4.7
"	"	Ebb	"	34	2.5
Plan B	Inbound	Flood	16,20	34	4.7
"	"	Ebb	"	34	2.5
"	Outbound	Flood	36	34	4.7
"	"	Ebb	"	34	2.5

¹Channel depth was increased one foot to allow comparison testing of the Existing Condition with the Plan conditions.

The current is the maximum current for flood and ebb tide and the corresponding tidal stage.

Turning maneuvers were performed with all inbound runs. For the existing channel, the turning maneuvers were performed in the intersection of the Claremont and Pierhead channels. Since the channel designs for Plans A and B were identical from the Ocean Terminal Pier out to the Anchorage Channel, inbound runs for Plan A were turned at the Claremont-Pierhead intersection and for Plan B, at the Anchorage-Claremont intersection. Through an oversight, the proposed turning basin off the end of the pier was not tested. The proposed turning basin will be superimposed on tracks of the turns made during the Plan A inbound runs which turned off the end of the pier to determine how the enlarged basin would have affected the results. Since the ship movement in the turning area is slow and under control of the tugs, the movement of the ship will not be significantly affected by the change in geometry of the bottom in this area except to allow additional maneuvering room.

Tests were chosen and conducted in a random order. The chosen test was performed and then removed from the list of conditions to be tested. This was done to prevent prejudicing the results as could happen if, for example, all existing conditions were run prior to running the plan conditions. The skill gained by familiarization with any one test condition could show the plans to be easier than they really were.

During each run, the characteristic parameters of the ship were automatically recorded every 5 seconds. These parameters included the position of the ship's center of gravity, speed, revolutions per minute (rpm) of the engine, heading, drift angle, rate of turn, rudder angle, port and starboard clearances, and tug forces.

The findings of the simulator study are based on pilot evaluations of individual runs, final questionnaires, ship control parameter plots, and ship track plots. The following section will present the evaluations of individual run ratings, final questionnaires, ship control parameter plots (speed, engine rpm, rudder angle, and port and starboard clearance distances) and ship track plots.

4 Study Results

Pilot Evaluations

After completing each test run, the pilot was asked to complete an evaluation of the run, rating the bank effects, current, wind, and ship handling. The ratings for each question for each test condition was averaged and these averages were plotted in the form of a bar chart to directly rate the same question for plan condition and operation mode. A higher rating value will usually indicate more difficulty or a more adverse condition than a lower rating. In addition, the plots for inbound runs rate the difficulty of the turning basin maneuver. An individual run evaluation is presented as Plate 17. The plots of the averaged pilots' ratings are presented in Plates 18-21.

Inbound, flood tide

The pilots rated the existing channel the same or lower than the plan channels for most questions (Plate 18). The rating differences were mostly small and insignificant. The rating differences for run difficulty, grounding (or striking an object) danger, and turn difficulty were among the largest. For the existing channel, the buoys are set well back from the channel edge. For the Plan A and B channels, the buoys were moved in to mark the exact edge of the deep water channel, so the buoys were only 300 feet apart, much closer to each other than with the existing channel. For all inbound runs, the ship was in ballast, drafting 16 ft at the bow and 20 ft at the stern. The vessels had much more maneuvering room than was indicated by the buoys marking the 34 ft mlw channel. The buoys being set much closer to each other tended to make the inbound runs more difficult to avoid striking a buoy. This is reflected in the higher ratings for total run difficulty and danger of striking an object for Plans A and B and turning maneuver difficulty for Plan A. The pilots also had difficulty with the limited field of view. As they looked out to the port or starboard, they could not see the ship, and therefore lost their perspective on where they were at and at what angle they were looking out relative to the ship direction. The pilots said that they relied almost exclusively on visual cues and rarely used radar. This probably contributed to the difficulty ratings, especially for the plan channels with unfamiliar buoy arrangements. The increase in turning maneuver difficulty of Plan B over

Plan A is due to the turn for Plan B being performed out in the Anchorage Channel in the stronger currents.

Inbound, ebb tide

Almost all questions were rated the same or lower for the existing channel than the plan channels (Plate 19). Again, most differences were relatively small. As with the flood tide runs, the run difficulty, attention required, danger of striking an object, and turning maneuver difficulty were higher with the plan channels than with the existing channel. This again is probably due to the positioning of the buoys with the plan channels being closer than with the existing channel and the limited field of vision. Turning out in the Anchorage Channel for Plan B was rated slightly less difficult than turning off the end of the pier with Plan A, but the Plan A rating is probably higher than the existing channel due to the placement of the buoys. The turning maneuver for the existing channel and Plan A channels should be almost identical, except for the placement of the buoys near the intersections of the Claremont and Pierhead Channels. The overall run difficulty ratings for the ebb tide condition were significantly less than for the flood tide conditions.

Outbound, flood tide

The existing channel rated the same or lower than the plan channels for all questions, except for danger of grounding or striking an object, where the plan channels were rated lower (Plate 20). Overall run difficulty was rated slightly higher for Plan A than the existing channel and slightly higher for Plan B than Plan A. Run difficulty and grounding danger are much less than with the inbound runs, reflecting the pilots verbal comments that the outbound runs are usually much easier than inbound runs. Most of the rating differences again are relatively small.

Outbound, ebb tide

Plan A was rated lower than the existing channel for all but danger of grounding or striking an object and Plan B nearly the same or lower than the existing channel for all questions except for run difficulty (Plate 21). Run difficulty and grounding danger were slightly higher when compared to the flood tide condition. This is probably due to the smaller underkeel clearances with the ebb tide condition, since the wind effect was rated almost the same for both tidal conditions and the current effect was rated higher for the flood tide than the ebb tide.

Summary

The pilots tended to rate the plan channels as being more difficult than the existing channel and Plan B as being slightly more difficult than Plan A. For the inbound runs, the placement of the buoys near the deep-water channel edge for the plan channels increased the perception of difficulty and danger. Although the plan channels were rated as more difficult, the differential of the ratings as compared to the existing channel were relatively small. Placing the buoys marking the plan channels away from the edge of the deep water channel would likely improve the pilots perception of the difficulty of the runs and the danger of striking one of the buoys. A large field of view would tend to improve the pilots' perception of the level of difficulty.

The pilots rated the turning maneuver in the Anchorage Channel to be more difficult than in the Claremont-Pierhead Channels for the flood tide condition and slightly less difficult with the ebb tide condition. The greater difficulty of the turning maneuver with Plan A than that of the existing channel condition is likely due to the placement of the buoys at the Claremont-Pierhead Channel intersection since the current and wind conditions are almost identical and the ballasted ship is basically unaffected by the increased width and depth of Plan A. Assuming that the ratings for the turning maneuver for the existing channel and Plan A would be almost identical if the buoys were moved away from the deep-water channel edge (and possibly lower for Plan A if the proposed turning basin had been tested), the turning maneuver in the Anchorage Channel would be rated significantly more difficult for both the flood and ebb tide conditions.

Final Questionnaires

After finishing all test runs, the pilots completed a final questionnaire to give their opinions on the project as well as the simulation. Some of the comments made by the pilots on the project follow:

1. Which of the channel designs did you prefer and why?

"I would prefer Channel (Plan) A because it gives an added element of safety with the greater width."

"Plan A. It offers the most room, 300 ft., all the way to (the) berth."

"Plan B is sufficient. Most ships will be turned inside off the (pier) where current is usually weaker. 250 ft with tug assistance and dead slow steerage is wide enough."

"I preferred the 300 ft (Plan A) as it gave greater safety for ship movement."

"300 ft channel (Plan A), because it gave more room to maneuver in and it gives you a better approach in making the outbound turn."

"300 ft width (Plan A) was preferable since maximum wind and current make approaches to entrances extremely difficult and require as much room as possible."

2. Will any of the proposed channel designs improve passage during peak tides?

"Yes. Outbound much easier and allows greater drafts. Inbound will always remain difficult under adverse conditions (i.e. high winds and peak currents)."

"It will make it easier to exit the terminal and have little effect on inbound approaches to the terminal."

"Yes. Any channel improvements will greatly improve the safety of ships using this channel. At the present time, ship movements during peak tides can be very difficult."

"The widening of the main channel entrance will help on the strong flood tide and southeast wind."

"Yes, a wider channel will be an improvement and make for easier passage."

"Plan A and B will both improve passages during peak tides, Plan A more than B..."

3. What is your opinion of turning in the Anchorage Channel as opposed to turning off the end of the Ocean Terminal pier?

"Turning in the Anchorage Channel is a valid option when coming in with flood current and southerly wind. It seems that turning at the end of the pier on flood current was extraordinarily difficult and turning outside somewhat less difficult. Generally though, turning at the end of the pier was preferable."

"I consider turning in (the) Anchorage Channel the most difficult and prefer to turn vessel off end of pier. The Anchorage Channel has the strongest cross-currents. Also, when turning in Anchorage channel you must back a much longer distance."

"Can be done (turn in Anchorage Channel) and have in the past when only one tug was available but prefer turning off pier."

"In the last 20 years I've only turned in the Anchorage Channel 6-7 times. I feel the current (except at slack) is too strong to consistently turn out in the Anchorage Channel."

"As a matter of practice, I prefer to turn off the pier. With a 760 ft ship, it will probably be necessary to strongly consider turning the ship in the Anchorage Channel for safety reasons."

"Prefer to turn off pier to minimize effects of current. If allowed to time turns to reduced current periods, turning in Anchorage Channel is a viable option."

4. Do you have any suggestions to improve navigation of the proposed channels (alignment, channel width, navigation aids, etc.)?

"At the present time when I have a ship going into Claremont that is under 580 ft and light draft on the bow (8-12 ft), I turn the ship off Dock 5. I think you should look at the idea of digging a little of the mud out near the Corps Pier and creating a turning basin to turn the 760' ships inside. This would mean we could turn where the wind and current had the least effect on a ship."

"I think that a red buoy placed near the pumphouse (mid-length of the Ocean Terminal Pier) would help to line-up an outbound vessel in the channel. It would act as a range with the first set of buoys."

"Perhaps 3 or 4 spar buoys could be put in between red and black nun off south corner of Caven Pt. pier and beginning of concrete dock at Claremont Terminal."

"The inner channel should be marked on both sides by buoys. The south side was marked years ago by spar buoys."

"I found it particularly difficult to navigate inbound when the buoys were placed on the edges of both the 250 and 300 ft channels. The wind and current effects made it almost impossible to safely navigate."

5. Do you have any suggestions for improving the simulation?

"The single screen leaves much to be desired. I found I was working with the radar more than the screen. Going to a real bridge layout and 3-5 screens would be a tremendous improvement."

"Perhaps adding tugs alongside when they are in use, wavelets caused by wind, water flowing around buoys, sound effects of wind and ships engine, perhaps using some sort of mouse to allow the pilot to look around as he would by turning his head."

"If possible try to improve depth perception especially when looking ahead and ship running ahead. With existing simulator, I find myself constantly checking radar for distance to buoys."

"It would help if the pilots had a more panoramic view so one could observe how the ship was maneuvering in relation to all of the buoys around it."

6. On a scale of 0 to 10 (10 being excellent), what is your overall opinion of the simulator and of the Claremont Terminal simulation?

"Given its present limitations, the simulation was very good and should give excellent results... "8"."

"9"

"8"

"8"

"8"

"8/9"

7. COMMENTS:

"I think perhaps the effect of wind was exaggerated and the tugs' power was underrated. In my opinion, a pair of 3000 HP tugs should be able to easily cope with the wind of 25 or so knots..."

"I consider outbound transits much easier than inbound. Backing a vessel with strong wind and current conditions is the most difficult. I prefer to turn off end of Caven Point pier when inbound..."

"When possible, channels should be wide and deep enough to allow for dead slow speed; use of half and full will cause the ship to squat. We presently use half and full so as to keep moving should the ship slow or rub bottom outbound."

"It would be helpful if a wider field of view was available so the pilots could react in a more timely fashion to changing situations."

"...I felt the simulation from inception to completion was professionally done and I felt comfortable performing the tasks required."

Navigation Parameter Plots

During operation of each test condition by each pilot, the navigation parameters of the ship which include speed, engine rpm, rudder position, rate of turn, drift angle, minimum clearance distance to the defined edge of the channel, both port and starboard, ship position, and tug forces were recorded every 5 seconds. All of the pilots' runs for the same test condition were combined and averaged to provide the data used for the plots. The ship parameters are plotted against the distance along track. Distance along track is the distance along a line beginning near the origin point (for inbound runs) and running near the centerline of the Anchorage and Claremont Channels into the terminal. All plots, whether inbound or outbound, are plotted versus this distance, with the outbound runs being plotted from right to left as they come outbound. Reference for the distance along track is provided in Plate 22. The

parameters that will be examined are ship speed, engine rpm, port and starboard clearances, and rudder position. Maximum engine rpm for the ship's used for this study was 100, so commands for one-quarter ahead would be 25 rpm and half-ahead would be 50 rpm.

Ship speed and engine RPM

Inbound, flood tide. The initial starting speed for the inbound runs was set at 5 knots. For the existing channel and Plan A channel, the pilots tended to maintain that speed as they approached the Claremont Channel and make the turn into Claremont (Plate 23). The pilots all tended to use about one-quarter ahead to maintain their speed up to the turn. For the existing channel, engine rpm was increased, indicating that several pilots used at least one-half ahead to help them make the turn. For Plan A, at least one pilot went to full ahead near the entrance of the Claremont Channel, an indication he was having difficulty making the turn. This probably led to more difficulty near the end of the pier, since the speed as they approached the end of the pier was approximately two knots greater than for the existing channel. For both conditions as they got near the end of the pier, the pilots backed the engine from half-astern to full astern in order to stop the ship and perform the turn. As they made the turn and started backing along the pier, they gradually reduced the engine rpm astern till they got near the dock, then they went to nearly half-ahead to stop the ship.

For Plan B, the pilots were required to turn in the Anchorage Channel. Speed and engine rpm were dropped earlier than with the existing or Plan A channels. As they approached the Claremont channel flare, the engine was stopped, then backed at near half-astern to bring the ship to a stop. At one point, at approximately 7000 feet along track, the rpm came to almost zero. At least one pilot had to come ahead with the engine to gain control and avoid striking the outer buoys marking the flare. This averaged in with most pilots going slowly astern yielded the near zero rpm. This pilot probably came ahead with one-half or full ahead, but only used it briefly, since the plot for speed at this point doesn't show any aberration. The engine was backed at near one-quarter astern for most of the transit through the Claremont Channel, occasionally being reduced to slow the backing speed of the ship. From the end of the pier to the dock, all plans had almost the exact same speed and very similar engine usage.

Inbound, ebb tide. Speed for the entire length of the run was almost identical for the existing channel and Plan A (Plate 24). Engine rpm for the existing and Plan A channels was very similar, both requiring much less engine power to make the turn than with the flood tide, indicating much less difficulty.

Plan B shows that the pilots started slowing almost immediately after starting their runs, using only slow to one-half ahead up to about 5,000 ft along track, then reducing rpm to near zero. As they reached the southern edge of

the channel flare, they started backing the engine slowly to reduce speed, then as they completed their turn, they backed more strongly to build up speed astern, then reduced the rpm to maintain a constant speed. The pilots backed from the Anchorage Channel to the end of the pier at about the same speed as they backed from the end of the pier into the terminal, approximately 4 knots. As they passed the end of the pier, they tended to run with nearly the same speed and engine rpm as with the existing and Plan A channels.

Outbound, flood tide. For all the outbound runs, the initial starting speed was 1 knot and the engine at dead stop. The pilots for all the test channels came to half ahead immediately (Plate 25), some using full ahead briefly to get their speed up more quickly. After pulling away from the dock they tended to run at about one-half ahead until they passed all the moored barges at approximately 12,000 ft along track. At this point with the existing channel, some of the pilots increased engine rpm. For Plan A, they tended to hold about one-half ahead and for Plan B, one or two pilots increase engine rpm. As the pilots reached the end of the pier, near 10,000 ft along track, five pilots went to full ahead for the existing channel, four pilots for Plan B and three for Plan A. By the time they reached the end of the Claremont Channel, all pilots for all channel conditions had gone to full ahead and remained that way through the completion of the runs, except for one pilot during a Plan B run that pulled back the engine briefly as he completed his turn into the Anchorage Channel.

Speed for all the channel conditions increased steadily from the beginning of the run to the end of the run. The Plan A and B runs are somewhat slower than the existing channel due to the larger draft (36 ft) of the ship used for the Plan A and B channels. Plan B had greater speed than Plan A due to more pilots going to full ahead earlier than with Plan A.

Outbound, ebb tide. As the pilots started the runs for each channel condition, they came almost immediately to one-half ahead (Plate 26). The southerly set due to the wind and the increased bank forces due to deepening the channel tended to make getting away from the dock more difficult than for the Plan A and B Channels. The pilots for Plan A used a large engine rpm briefly to help them pull away from the dock. As they pulled away from the dock, the rpm for Plan A tended to average 10 or 15 rpm higher than the existing or Plan B channels. Engine rpm for the existing and Plan B channel was approximately the same until the pilots reached the end of the pier. As the runs passed the end of the pier, Plan A rpm increased only slightly, but the existing and Plan B engine rpms increased to exceed that of the Plan A channel. As they approached the start of the turn at 8,000 ft along track, almost all of the pilots for the existing and Plan B channels went to full ahead, but the Plan A channel only had four pilots to go to full ahead. As they completed the turn near 6,000 ft along track, the Plan A pilots all went to full ahead, one pilot from the existing channel came back to one-half ahead and two pilots for Plan B came back to one-half ahead till near the end of the runs.

Speed for all the channel conditions steadily increased throughout the runs. Again the existing channel was run somewhat faster, due to smaller draft of the vessel used with the existing channel. Plan A was faster than Plan B from the start of the runs to near the start of the turn, due to more engine rpm being used early for Plan A. As they came through the turn, Plan A and B were almost exactly the same speed, then Plan A was faster to the end of the run due to two pilots pulling back to one-half ahead for Plan B after completing the turn.

Minimum clearance distances and rudder position

Clearance distance is not plotted up to 7500 ft along track. This is due to the relative width of the Anchorage Channel as compared with the Claremont Channel. Distance is measured from the ship to the edge of the defined channel. With the ship in the Anchorage Channel, clearances in excess of 1,000 ft were shown. To reduce the clearance plots to a more meaningful scale, the clearance distances in the Anchorage Channel were removed and only the clearance distances in the Claremont Channel, starting at the channel flare were plotted.

Clearance distances for inbound and outbound runs will be discussed using different channel limit criteria for each condition. For all the outbound runs, clearances are defined to the limits of the deep-water channel. For the inbound runs, the clearances are defined to the 20-ft contour line which approximately represents the available channel for the ballasted vessels. Normally clearances are defined as port or starboard clearance (clearance from the port or starboard side of the ship). When the ships are performing turning basin maneuvers off the end of Caven Point Pier, port clearance to the southern channel edge as the ship is coming in bow first becomes port clearance to the northern channel limit as the ship rotates and begins backing into the terminal. To avoid confusion, clearances for this study will be defined to the north or south channel limits.

Inbound, flood tide. Clearances for the existing channel and Plan A were similar as the vessels entered the Claremont Channel and approached the turning basin (Plate 27). The large values of north clearance and relatively small values of south clearance for the existing and Plan A channels in the turning basin area are somewhat deceiving since some of the pilots turned the ship in a counterclockwise direction instead of the more routine clockwise direction. The pilots who turned counterclockwise went much further south into the Pierhead Channel than did the other pilots and their clearance distances, averaged with the other pilots clearances, would yield a large north clearance and a smaller south clearance. The average negative south clearance opposite the end of the Caven Point Pier for the existing channel is due to one pilot who turned counterclockwise and went well outside the south channel limit at the southwest corner of the Claremont-Pierhead Channel intersection. The near zero north clearance for Plan A near the end of Caven Point Pier is due to one pilot who went well up onto the pier. Plan B shows adequate

clearance on both sides up to the end of the pier with the pilots tending to stay slightly closer to the southern channel edge. As the ships backed into the terminal from the end of the pier, all of the plans are very similar. With all plans, there was a tendency to get very close to the south edge of the channel near mid-length of the pier, then work over to be near to or slightly outside the north channel limit near the completion of the runs. The values of rudder used vary widely by plan. For the existing and Plan A channels, the pilots let the current and wind turn them into the Claremont Channel, then used starboard rudder to hold up as they passed to the turning basin. With the existing channel, most pilots used hard right rudder to turn into the turning basin. With Plan A, the pilots averaged first using port rudder then going back to starboard rudder as they started their turns. This is again likely due to the pilots who turned opposite the direction of the other pilots. Once turned, rudder was occasionally used to help correct position in the channel. For Plan B, the pilots used little rudder after getting up to the channel flare, using mostly the tugs to turn and hold their position within the channel.

Inbound, ebb tide. Clearances for the existing condition and Plan A are similar from the channel flare up to the turning basin (Plate 28). For the existing condition, all the pilots turned the vessel clockwise with most turning well off the end of the pier. The large average of north clearance (up to about 700 ft at 10,000 ft along track) is likely an anomaly associated with the recording and averaging of a large number of clearance values while the ships were rotating in the turning basin. This is also the likely case for the very low south clearances from about 9,500 to 10,000 ft along track. For Plan A, all the pilots turned clockwise in the basin. The turns tended to be made further into the basin, as reflected by the smaller north clearances as compared to the existing channel. As the turns were completed with the existing and Plan A channels, the current and wind tended to set the vessel down to the south and hold it there. For Plan B, the pilots tended to back into the Claremont Channel along the southern edge and remain there. With all plans, as they backed along the length of the pier, they set outside the south channel limit at about 13,000 ft along track, then as they worked back into the channel, they tended to go near to or slightly out of the north edge of the channel near the completion of the runs. Rudder usage for all plans was similar until they approached the channel flare. With the existing condition, the pilots used a long gradual application of port rudder to turn into the Claremont Channel, then maintained port rudder to hold up against the set of the wind and current until they reached the turning basin where they used starboard rudder to initiate their turn. With Plan A, the pilots applied a larger port rudder for a shorter duration than with the existing channel. This is due to the placement of the channel buoys being set in to mark the edge of the deep-water channel for Plan A, offering a smaller clearance between the buoys than with the existing channel. As they approached the basin, little rudder was used until they got into the basin where some port rudder was used. The turns were made mostly under tug control. The use of port rudder to make a clockwise turn is not readily explainable. It would seem likely that one or more pilots applied a large value of port rudder (or did not cancel an earlier command for port rudder) for an extended period while in the basin. This, if averaged in

with other pilots using little or no rudder would yield the average as plotted. For Plan B, the pilots used starboard rudder for a extended period as they approached the flare to turn the vessels to prepare to back into the Claremont Channel. As they started backing into the channel, rudder was brought to midships. For all plans, rudder was occasionally used as the ships backed along the length of the pier, along with engine ahead, to reestablish position within the channel.

Outbound, flood tide. The existing condition maintains a negative south clearance for almost the entire length of the Claremont Channel (Plate 29). This was probably due to the pilots holding up against the northerly set of the currents and wind. The negative north clearance from approximately 14,000 to 12,000 feet along track is due to the angle that the ship is holding to compensate for the wind and current set, actually causing negative clearance on both sides of the channel for a short span near 12,000 feet along track. The plots for both Plan A and B show that the pilots were able to stay within the defined channels. The south clearances show that the pilots tended to use a similar path for both channels which would be near mid-channel for Plan A and slightly favoring the north side for Plan B. The reduction in channel width is along the north side for the outbound runs, which is clearly indicated in the north clearances.

Rudder usage for all three of the channel plans was very similar. The plots indicate that the pilots maintained more starboard rudder for a longer period of time with the plan channels versus the existing channel as they turned into the Anchorage Channel (5,000 to 8,000 feet along track), but this is probably due to the draft of the loaded vessel for the plan channels being 36 feet versus 30 feet for the existing channel and less maneuverable.

Outbound, ebb tide. The plots for north and south clearances for the existing channel are almost identical to those with the flood tide (Plate 30). The pilots averaged a negative south clearance for almost the entire length of the Claremont Channel and were out along the north side as they passed the moored barges. For Plan A and B, there were no problems with clearance, except at the very beginning of the runs where they start near the dock and slightly outside the defined channel. For the ebb tide runs, the pilots all tended to run toward the northern side of the channel to compensate for the southerly set.

The rudder usage plots for all the channel conditions are very similar. The pilots tended to vary on how they turned out into the Anchorage Channel. With the existing condition, they started the turn at the beginning of the flare and maintained fairly constant rudder until they completed the turn. With Plan A, they again started the turn at the beginning of the flare, but used less rudder than with the existing condition until they got well out into the Anchorage Channel where they applied more rudder and then used the large rudder setting longer than with the existing condition. For the Plan B Channel, the pilots started their turn a few hundred feet before reaching the beginning of the flare, then gradually increased the rudder till they got well out into the Anchorage

Channel, then gradually reduced it. The reasons for these differences are not clear, but all of the turns were made successfully and none of the pilots indicated any problems associated with the turn.

Summary

The parameter plots indicate that inbound or outbound runs with the Plan A and B channels can be performed with no significant increase of engine power or rudder usage over that used for the existing condition runs. Both of the plan channels show major improvement in clearance distances for the outbound runs as compared with the existing condition. Adequate clearances were maintained while backing the entire length of the Claremont Channel after turning in the Anchorage Channel.

Ship Track Plots

A complete set of combined ship track plots for the channel test conditions is presented in Plates 31-42. A tabulation of the individual piloted runs and their results is presented in Table 1. For the inbound runs, with the ship in ballast at 16-ft bow and 20-ft stern, a 20-ft and 16-ft deep channel limit will be used for channel limits. As stated previously, the enlarged turning basin proposal was not tested directly. The proposed turning basin limits are superimposed on the track plots of the inbound runs for Plan A to determine how the enlarged turning basin would have affected the test results that were performed without the basin. For outbound runs, only the deep water channel is shown and used for channel limits.

Inbound, flood tide

Existing Channel. The pilots split on how they chose to enter the Claremont Channel (Plate 31A and 31B). Four came in along the southern edge of the flare and the other two allowed themselves to be set toward the northern edge of the flare, then drove back against the current and wind to come into the Channel. All of the pilots tended to be set toward the northern side of the Claremont Channel with two pilots going slightly outside the 20-ft draft limit. Most of the pilots chose to turn the ship by going bow first off the end of the pier and turn clockwise. One pilot, due to the set he had as he entered the Claremont-Pierhead intersection, chose to put the bow to the south and turn in a counter-clockwise direction. According to verbal comments made by this pilot, he occasionally performed this maneuver when he is having difficulty getting the stern of the ship to come up into the strong wind and/or current from the south. This pilot went outside the 20-ft and 16-ft channel limits with the bow of the ship, so grounding would probably have occurred. As all the pilots backed into the terminal, they tended to follow a nearly uniform path, centering the deep water channel. One pilot allowed his ship to

drift near the pier before coming back to mid-channel. This pilot went outside the 20-ft channel limit briefly at approximately mid-length of the pier.

Plan A Channel. As with the existing channel condition, four of the pilots came in along the southern edge of the flare and the other two drifted to the northern edge, then drove into the currents and wind to come into the channel (Plate 32A and 32B). All the runs were set to the northern edge of the Claremont Channel with three pilots going slightly outside the 20 ft channel limit. Three of the pilots turned clockwise off the end of the pier and the other three turned counterclockwise. One pilot ran over the northern buoy at the Claremont Channel flare, another over the northern buoy marking the Claremont-Pierhead Channel intersection and another edged the southern buoy opposite the end of the pier. One pilot struck the pier approximately 250 feet from the end of the pier. This was likely due to excessive speed as the ship entered the turning area. Backing into the terminal was performed very similar to that of the existing channel with all pilots running toward the northern side of the channel and one pilot going well outside the 20 ft channel limit near mid-length of the pier, as was the case during the existing condition. With the proposed turning basin in place, the pilots would have additional room along the northern edge of the channel to allow their ship to set to the north with the wind and current. Since the tendency was for the stern to set north, turning counterclockwise would likely be easier than turning clockwise with the flood current. This additional room would have eliminated the groundings or near groundings to the south in the Pierhead Channel and also striking the pier since the pilots could have turned further out off the pier.

Plan B Channel. The pilots were required to turn in the Anchorage Channel and back into the Claremont Channel (Plate 33A and 33B). Most of the pilots tended to go to the northern side of the flare, hold up, let the stern come up to the north clockwise, then back into the channel with the assistance of two tugs. One of these pilots approached with hard left rudder and actually performed a 270-degree turn, going well north before driving to the southern edge of the flare near the buoy, then backing into the channel, striking the buoy as he backed. This pilot also went well beyond the 20-ft channel limit and edged outside the 16-ft channel with the bow along the northern edge of the channel and struck the northern buoy marking the Claremont-Pierhead intersection. One other pilot also went out of the 20-ft channel limit, but only with the bow and then only briefly. One pilot chose to start his turn well south of the channel flare and let the current and wind push his ship laterally to the north as he backed. All the pilots stayed near the northern channel edge till they reached the end of the pier. As they passed the pier, the pilots tended to have better control and completed their runs into the terminal near mid-channel, except for one pilot who went slightly out of the 20-ft channel limit near mid-length of the pier, as was the case for both the existing channel and Plan A. The buoy marking the transition from the 250-ft to 300-ft channel was struck by one pilot.

Inbound, ebb tide

Existing Channel. Most of the pilots chose to drive directly into the Claremont Channel, starting out near the right side of the channel at the outer northern buoy, anticipating the set from the current and wind from the north (Plate 34A and 34B). One of these pilots went well north of the channel flare, either expecting the set to start earlier than it did or expecting a greater set than he got, and struck the northern buoy marking the flare. The other pilot came to a stop in the Anchorage Channel, used the tugs, wind, and current to rotate the ship into alignment with the Claremont Channel, then proceeded into the channel. One pilot skirted the edge of the 20-ft channel limit along the northern side of the channel. All the pilots appeared to make the turning maneuver off the end of the pier with little difficulty. All the pilots turned clockwise, putting the bow up into the channel off the end of the pier. One pilot went slightly outside the 20-ft channel limit to the north, but was well within the 16 ft limit, so he probably would not have grounded. One of the tracks shows the bow coming near the southern edge of the 20-ft channel. This was due to the pilot completing his turn too far south and almost striking the southern buoy opposite the end of the pier with the stern of his ship. To avoid this, he put the rudder hard right and came ahead with the engine. This pushed the bow of the ship well down into the Pierhead Channel, south of the Claremont Channel. He then backed and used the tugs to bring him into alignment with the Claremont Channel. Backing from the end of the pier into the terminal appears to be similar in difficulty as with the flood tide condition. Near the completion of the run at the terminal, one pilot went well outside the 20-ft channel limit. Prior to reaching the end of the dock, he was backing along the southern edge of the channel. To avoid the barges moored at the end of the dock, he had the tug push the stern well up to the north. He may have been expecting the wind from the north to slow the northward motion. When it became apparent that the ship would not stop in time, he had the tug push the stern of the ship toward the south. This caused the bow to accelerate toward the north. As the stern of the ship moved out of danger, the pilot applied hard right rudder and engine ahead to brake the counterclockwise rotation of the ship. As the ship came back toward parallel with the dock, the run was ended.

Plan A Channel. Four of the pilots started at the southern edge of the flare and made wide sweeping turns into the Claremont Channel, completing the turns near the northern edge of the channel at the buoy (Plate 35A and 35B). Two pilots chose to go further north, then make sharper turns into the Claremont Channel. One of these pilots did not anticipate the wind and current set correctly and ran over the northern buoy at the flare. One other pilot hit this buoy, but only a glancing blow. All of the pilots completed the turning maneuver without excessive difficulty, except for avoiding the buoys along the southern edge of the Claremont Channel. The buoy marking the flare was struck once, the buoy marking the intersection of the Claremont and Pierhead Channels three times, and the buoy opposite the end of the pier once. There were several instances where the ship went outside the 20-ft channel limit, but all were out briefly and most of them were out with the bow which was

drafting less than 20 feet. Backing into the terminal was completed mostly without incident. One pilot did allow his ship to come very near the two moored barges just outside the terminal, but did not strike either of them. One pilot allowed the ship to strike the dock at the completion of his run. With the proposed basin in place, the pilots could "drive " into the basin along the northern edge of the channel to compensate for the current and wind set to the south, then with tug assist, began turning the vessel. This would likely eliminate the groundings along the southern edge of the channel between the channel flare and the Pierhead Channel.

Plan B Channel. Five of the six pilots turned in or near the flare. Most came up near the northern edge of the flare, stopped, then let the tugs, current, and wind turn the bow clockwise, then backed into the channel (Plate 36A and 36B). One pilot went well north of the flare and let the ship drift south as he performed his turn. The sixth pilot started his turn out in the Anchorage Channel south of the flare then backed against the current up into the channel. One pilot struck the southern buoy marking the Claremont-Pierhead intersection. The pilots all backed past the end of the pier with little apparent difficulty. As they approached the terminal, one pilot allowed his ship to set down near the outermost moored barges, but did not strike them. Near the end of the run, one pilot was coming in along the southern edge of the channel. As he neared the moored barges, he had the tug push the stern toward the north. He apparently had the tug push too long or hard or was expecting a stronger southerly set due to the wind. He allowed the ship to come near the northern limits of the 20-ft draft channel, briefly going outside the 20-ft channel opposite the dock.

Outbound, flood tide

Existing Channel. Most of the pilots tended to set to the northern edge of the channel as they came past the end of the dock and the moored barges (Plate 37). As they reached mid-length of the pier, they started getting their set for the wind and current and tended to run nearer the southern edge of the channel. As they passed the end of the pier, they still tended to run near or outside the defined channel limits out to the flare. Most of the pilots were running well south of the defined channel as they reached the flare, with two pilots being completely outside the channel. The channel, especially near the flare, is only two or three feet deeper than the surrounding bottom elevations, so bank forces are not very strong. The pilots all turned into the Anchorage Channel with little difficulty, finishing their run near the center of the Anchorage Channel.

Plan A Channel. As the pilots began their runs, they mostly tended to stay near the center to southern edge of the channel (Plate 38). Only one pilot went up near the northern edge of the channel opposite the moored barges. As they approached the end of the pier, all the pilots tended to run from the center of channel to near the northern edge. As they passed the end of the pier, all pilots pushed down near the southern edge of the channel to prepare for the

northerly set from the currents and wind. One pilot ran slightly outside the defined southerly edge of the channel between the inner and outer buoys. As the pilots passed the outer buoys they made their turns into the Anchorage Channel, completing their runs near the center of the Anchorage Channel.

Plan B Channel. As the pilots started their runs, all but one tended to stay near the center of the channel as they passed the moored barges (Plate 39). One pilot went up along the northern channel edge and went slightly outside the channel for about two ship lengths. As they approached the transition from the 250-ft to the 300-ft width channel, all the pilots tended to come north to come closely by the northern marker buoy. One pilot slipped out of the channel briefly just before reaching the buoy. As they passed the end of the pier, they all went down along the southern edge of the channel to hold against the wind and current set, as they did with Plan A. One pilot came alongside the southern channel limit as he approached the outer buoys, but did not go outside the channel. All the pilots started their turns as they passed through the outer buoys and completed their runs near the center of the Anchorage Channel.

Outbound, ebb tide

Existing Channel. All of the pilots tended to stay near the center of the channel from the start of the run to mid-length of the pier, but all went out on the northern or southern limit of the channel between these points (Plate 40). Further out along the pier, all the pilots tended to group along the southern edge of the channel, most going out of the channel limit. As they passed the end of the pier, most continued along the southern edge of the channel, mostly centering the southern channel limit. One pilot went up along the northern channel limit, going slightly out of the channel and remaining that way until reaching the flare. As the pilots passed through the outer buoys, they all started their turns and completed their runs near the center of the Anchorage Channel.

Plan A Channel. At the start of most of the runs, the pilots remained very close along the southern channel limit (Plate 41). The combination of the strong southerly wind and the increased bank suction with the deeper channel made pulling away from the south side more difficult than with the flood tide condition. One pilot pulled away from the dock more forcefully than the others and actually went out of the channel along the northern edge as he passed the moored barges outside the terminal. After passing mid-length of the pier, all the pilots tended to stay from mid-channel to near the northern channel limit. One pilot grazed the northern inner buoy marking the Claremont-Pichead intersection. As the pilots approached the flare, they all returned to near mid-channel. The pilots started their turn into the Anchorage Channel as they passed through the outer buoys or immediately after passing through them and completed their runs near mid-channel of the Anchorage Channel.

Plan B Channel. As with Plan A, the pilots started their runs from center of channel to near the right channel edge (Plate 42). As they approached the buoy marking the transition from the 250-ft to the 300-ft channel, they grouped near mid-channel, then after passing the end of the pier, they moved to mid-channel of the 300-ft channel. Most of the pilots remained near mid-channel till they passed through the outer buoys and into the flare. One pilot moved toward the northern channel edge, starting at the inner buoys, ran along the northern channel edge, coming near the northern buoy marking the flare, then turned. The pilots varied from left-center to right-center of the Anchorage Channel at the completion of their runs.

5 Conclusions and Recommendations

Limitations of the Study

There are several limiting factors in determining test results and conclusions that can be reached. The simulator only provided one viewing screen, showing about a 40-degree field of view. Most pilots said that they rarely used the radar to make the transits either inbound or outbound, but relied on visual references and cues. Although the objects that they normally use were present in the visual scene, the restricted field of view limited their usefulness since it required that the look around feature be used constantly to provide them the field of view that they normally would have from the ship's bridge. All the pilots tended to rely more heavily on the radar image rather than moving the viewing angle which probably effected their operational technique. The ship model used for testing was derived from design characteristics of a steam turbine vessel. The pilots stated that there are almost none of this type vessel that use this port. They said that almost all the vessels that call on this port are diesel, which have a much quicker engine response and better backing characteristics than steam turbine vessels. The numerical ship model engine response and handling characteristics were modified to improve response and handling, but the ship was still described as being sluggish when compared with most vessels that they have piloted.

Testing was performed going outbound at the strength of ebb tide (as a worst case scenario), which is not normal practice for the existing channel. The proposed channel deepening to 34 ft mlw would provide a larger "window" of operation than at present. The ebb tide condition tested for the plan channels is the latest point of the "window" that a vessel loaded to 36 ft could leave the port and also the strongest ebb tide current. With the tidal stage advantage of 2.5 ft, the vessel would be going out with less than one ft of underkeel clearance, but according to pilots' comments, this is not unusual for present operations with flood tide. Testing with ebb tide was performed to determine if there were any adverse conditions that would be associated with this tidal condition. In practice, if the vessel was going out later than at peak flood tide, it would probably be taken out earlier than at maximum ebb tide current (during the declining flood tide or early in the ebb tide) when there

was more water available and less current, but for testing, the strongest current that the pilots would be expected to operate in is more desirable. Therefore, the highest ebb tide current at the latest point of the "window of opportunity" was used. Comparative testing of the plan channels with the existing channel for this condition is not directly possible since there is not enough underkeel clearance during peak ebb tide for the existing channel with the vessel drafting 30 ft. To make a comparison possible, the channel depth was increased one ft to 28 ft and with the tidal stage of 2.5 ft, this would give an underkeel clearance of 0.5 ft, the same as that used for the plan channels. Again, operation during this portion of the tidal cycle would not normally be expected, but this represents the extreme limits of operation, as does the current and wind, that a pilot would attempt to navigate the channel. If the channel can be navigated successfully in the extreme conditions, the channel should be adequate for navigation in normal operating conditions.

As previously mentioned, the proposed turning basin along the northern edge of the channel between the channel flare and the Pierhead Channel was not tested. The outline of the turning basin limits was superimposed on the track plots of the inbound runs for Plan A to help determine how the basin would have improved their passage through the outer Claremont Channel and their turns off the end of the pier. The availability of the extra area would likely have influenced how the pilots chose to enter the channel and turn. Taking the strategies that the pilots used to perform the turns for Plan A, the current conditions, and the wind conditions, an extrapolation of how the basin would have affected their operation can be made.

Although the previously described limitations made the operation for the pilots more difficult, they also will tend to make the results of the study more conservative. The wind and current conditions are set to be those which would be the most difficult the pilots would expect to navigate in. The pilots' ability to successfully navigate the test channels with the extreme current and wind conditions, along with the restrictions of visual field of view and ship handling would tend to confirm that the channels could be transited in the prototype under more favorable conditions with acceptable levels of difficulty and safety.

Conclusions

Some of the pilots commented that coming inbound with a ballasted ship would be basically unaffected by whatever changes are made in the depth and width of the Claremont Channel. This is a logical and valid assumption. The currents run almost perpendicular to the alignment of the channel and were negligibly different from the existing channel to either of the plan channels. The amount of navigable channel available for the pilots to use will be unaffected, since in the ballast condition, they are only restricted by the limits of 20-ft depth. The only changes that would affect inbound traffic is placement of the buoys, whether the ship will turn off the end of the pier, as they

do now, or out in the Anchorage Channel, and whether the proposed turning basin is constructed.

The pilots tended to rate the Plan A channel as more difficult than the existing channel and Plan B slightly more difficult than Plan A. As discussed in the pilot evaluations, the buoys were set along the edge of the channel for Plan A, much closer together than the existing buoys are. For Plan B, an additional buoy was added to mark the transition from the 250- to 300-ft channel, also along the channel edge. For the existing channel conditions, there were no buoy strikes during the inbound flood tide runs and one during the ebb tide. For the Plan A channel, there were four buoy strikes during the flood tide and seven during the ebb tide. Using the assumption stated in the previous paragraph, it becomes apparent that the increase of the handling difficulty rating with inbound ships in ballast with Plan A over the existing condition was a function of buoy placement. This is supported by a statement made by one pilot in his final questionnaire that the buoys should be placed further away from the channel edge. It appears that the buoy placement for the existing channel tends to mark the 20-ft contour for inbound, light-loaded (or ballasted) vessels and the deeper navigation channel for the loaded outbound vessels is unmarked. If the buoys had been placed away from the channel edge for Plan A and B as they were for the existing condition, the difficulty of the inbound runs with Plan A and B should be almost the same as for the existing channel, if not less. The buoy placement likely increased the turning basin maneuver rating for Plan A also. The turning basin maneuver in the Anchorage Channel for Plan B is rated higher than the turning maneuver off the end of the pier for the existing condition for both ebb and flood tide and higher than Plan A for the flood tide. If the proposed turning basin had been available to the pilots for Plan A, the rating for Plan A would probably be much lower and the differentials to Plan B much greater. Although the averaged clearance distance indicated that turning in the Anchorage Channel could be done, examination of parameter plots, track plots, and pilots' comments indicate that turning in the Anchorage Channel during peak ebb and flood tide currents can be performed but is likely too difficult to be performed safely on a routine basis.

The outbound runs were rated by the pilots to be slightly more difficult for Plan A than the existing channel and slightly more difficult for Plan B than Plan A. The track plots for both Plan A and Plan B show much better runs with regard to staying within the defined channel than the existing channel. Plan A had only one pilot going outside the channel limit during an ebb tide run and Plan B had only one pilot going outside the channel limit during a flood tide run whereas the existing condition runs had many incidences of going out of the defined channel both to the north and south. None of the track plots clearly indicate why the pilots perceived the plan channels to be more difficult. The higher difficulty ratings for the plan channels may again be due to the placement of the buoys.

Based on the real-time pilot runs, the pilots' individual run evaluations, and

comments made on their final questionnaires, the following preliminary conclusions were reached:

- a. Inbound ships in ballast will be mostly unaffected by channel deepening or widening, except for positioning of the channel buoys and the proposed turning basin.
- b. Plan A appears to provide adequate maneuvering room for the outbound transits with either the flood or ebb tide condition based on clearance distances and track plots.
- c. Plan B appears to provide adequate maneuvering room for the outbound transits with either the flood or ebb tide condition, but provides less maneuvering room from the terminal to the end of Caven Point Pier than Plan A.
- d. The design of the flare from the Claremont Channel to the Anchorage Channel is adequate.
- e. Turning in the Anchorage Channel can be performed but is more difficult than turning off the end of the pier and increases the difficulty of the inbound transit due to backing a greater distance in strong cross currents and wind.
- f. The proposed turning basin would improve inbound passage and turning during either ebb or flood tide.

Recommendations

Based on the pilot test results, comments, and conclusions reached, WES proposes the following:

- a. Adopt either the Plan A or Plan B channel design. Both channel designs appear adequate for safe navigation, but Plan A provides slightly more clearance. If possible, remove the slight "dog-leg" in the channel so only one set of range markers would be needed.
- b. Set the buoys to mark the 20-ft channel contour for inbound traffic and install ranges to mark the 34-ft navigation channel for outbound traffic.
- c. Adopt the proposed turning basin, dredged to -20 ft mlw if turning is to be performed off the end of the pier. Suggested modifications to the turning basin design and suggested marking of the basin are in Plate 43.
- d. Restrict turning in the Anchorage Channel to slack or near slack tide conditions or provide additional channel by dredging to -20 ft mlw along

the northern edge of the channel as shown in Plate 44.

- e. Dredge the southwest corner of the Claremont-Pierhead Channel intersection to provide additional area for turning counterclockwise off the end of the pier as shown in Plate 44.

Table 1
Tabulation of Individual Pilot Runs

TABULATION OF INDIVIDUAL PILOT RUNS

PAGE 1


PILOT	PLAN	TIDE	DIRECTION	FIGURE NO.	RESULTS
C	EXISTING	EBB	INBOUND	1	Bow slightly outside 20' contour near entrance
-	-	-	OUTBOUND	2	Out along southern edge of channel
-	-	FLOOD	INBOUND	3	OK
-	-	-	OUTBOUND	4	Out to north near terminal, well out on south from end of pier to flare
-	PLAN A	EBB	INBOUND	5	Struck northern outer buoy and buoy opposite end of pier
-	-	-	OUTBOUND	6	OK
-	-	FLOOD	INBOUND	7	OK
-	-	-	OUTBOUND	8	Out slightly to south between inner and outer buoys
-	PLAN B	EBB	INBOUND	9	Struck southern buoy at flare
-	-	-	OUTBOUND	10	OK
-	-	FLOOD	INBOUND	11	Struck southern inner buoy, out to north near mid-length of pier
-	-	-	OUTBOUND	12	Out to north near mid-length of pier
D	EXISTING	EBB	INBOUND	13	Struck northern buoy marking flare, bow out over 20' contour
-	-	-	OUTBOUND	14	Out to south near end of pier, out to north just before the flare
-	-	FLOOD	INBOUND	15	OK
-	-	-	OUTBOUND	16	Out to north near terminal, well out to south from end of pier to flare
-	PLAN A	EBB	INBOUND	17	Struck northern outer buoy and southern inner buoy, out to south of inner buoy
-	-	-	OUTBOUND	18	Out to north near mid-length of pier and near north inner buoy, struck north inner buoy
-	-	FLOOD	INBOUND	19	Struck outer northern buoy, struck pier
-	-	-	OUTBOUND	20	OK
-	PLAN B	EBB	INBOUND	21	OK
-	-	-	OUTBOUND	22	Out very slightly (< 10') to north near outer buoy
-	-	FLOOD	INBOUND	23	Struck southern outer buoy, out to north near inner buoy
-	-	-	OUTBOUND	24	Slightly out to north near buoy marking channel width change, near south edge at outer buoy
E	EXISTING	EBB	INBOUND	25	Stern out slightly to south near southern inner buoy
-	-	-	OUTBOUND	26	Out to north near terminal, out to south from end of pier to flare
-	-	FLOOD	INBOUND	27	Stern out to north of 20' contour between buoys, bow out slightly in basin, out to north near mid-length of pier
-	-	-	OUTBOUND	28	Out to north opposite of terminal, out to south from mid-length of pier to flare
-	PLAN A	EBB	INBOUND	29	Struck southern inner buoy, stern out to south at same buoy
-	-	-	OUTBOUND	30	OK
-	-	FLOOD	INBOUND	31	Out to north between buoys and to north at mid-length of pier
-	-	-	OUTBOUND	32	OK
-	PLAN B	EBB	INBOUND	33	Struck southern inner buoy, bow out slightly to south over 20' contour near mid-length of pier
-	-	-	OUTBOUND	34	OK
-	-	FLOOD	INBOUND	35	Struck northern inner buoy, struck buoy marking channel width change
-	-	-	OUTBOUND	36	OK

Table 1 (Concluded)

TABULATION OF INDIVIDUAL PILOT RUNS

PAGE 2

PILOT	PLAN	TIDE	DIRECTION	FIGURE NO.	RESULTS
F	EXISTING	EBB	INBOUND	37	OK
	-	-	OUTBOUND	38	Out to south for most of Clermont Channel
	-	FLOOD	INBOUND	39	OK
	-	-	OUTBOUND	40	Out slightly to north near terminal, out slightly to south near flare
	PLAN A	EBB	INBOUND	41	Struck northern outer buoy
	-	-	OUTBOUND	42	OK
	-	FLOOD	INBOUND	43	OK
	-	-	OUTBOUND	44	OK
	PLAN B	EBB	INBOUND	45	OK
	-	-	OUTBOUND	46	OK
G	-	FLOOD	INBOUND	47	OK
	-	-	OUTBOUND	48	OK
	EXISTING	EBB	INBOUND	49	Out to north opposite of terminal
	-	-	OUTBOUND	50	Out to south from end of pier to flare
	-	FLOOD	INBOUND	51	Out to north between buoys, well out to south opposite end of pier
	-	-	OUTBOUND	52	Very near edge of channel to south
	PLAN A	EBB	INBOUND	53	Struck southern inner buoy
	-	-	OUTBOUND	54	OK
	-	FLOOD	INBOUND	55	Out to north near inner buoy, struck same buoy, out to south opposite end of pier, out to north opposite terminal
	-	-	OUTBOUND	56	OK
H	-	EBB	INBOUND	57	Out to north opposite terminal
	-	-	OUTBOUND	58	OK
	-	FLOOD	INBOUND	59	OK
	-	-	OUTBOUND	60	OK
	EXISTING	EBB	INBOUND	61	OK
	-	-	OUTBOUND	62	Out to south for most of Clermont Channel
	-	FLOOD	INBOUND	63	OK
	-	-	OUTBOUND	64	Out to north near terminal, out to south near flare
	PLAN A	EBB	INBOUND	65	OK
	-	-	OUTBOUND	66	Slightly out to south from terminal to mid-length of pier
I	-	FLOOD	INBOUND	67	Out to north at inner buoy, struck same buoy, out to south opposite end of pier
	-	-	OUTBOUND	68	OK
	PLAN B	EBB	INBOUND	69	OK
	-	-	OUTBOUND	70	Very near to south edge of channel near mid-length of pier
	-	FLOOD	INBOUND	71	Struck northern inner buoy
	-	-	OUTBOUND	72	OK







Plate 2






Plate 4




Plate 5




Plate 6




Plate 7




Plate 8




Plate 9





Plate 10







Plate 12







Plate 14






Plate 16

CLAREMONT TERMINAL CHANNEL SIMULATION STUDY
PILOT RATINGS

PILOT: _____
 RUN CODE: _____
 START TIME: _____

DATE: _____
 OUTPUT FILE: _____
 END TIME: _____


The purpose of this questionnaire is to document your evaluation and observations concerning the simulator run you have just completed. Feel free to make any specific comments you feel will be helpful in interpreting your ratings.

1. Rate the difficulty of the run.
 EASY 0 1 2 3 4 5 6 7 8 9 10 VERY DIFFICULT
2. Rate the effects of the current on the ship.
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 TREMENDOUS
3. Rate the bank effects on the handling of the ship.
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 TREMENDOUS
4. Rate the wind effects on the handling of the ship.
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 TREMENDOUS
5. Rate the amount of attention required.
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 ALL OF IT
6. Rate the danger of grounding or striking an object.
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 TREMENDOUS
7. Rate the realism of handling the simulator.
 BAD 0 1 2 3 4 5 6 7 8 9 10 VERY GOOD
8. Rate the realism of the current effects.
 BAD 0 1 2 3 4 5 6 7 8 9 10 VERY GOOD
9. Rate the realism of the bank effects.
 BAD 0 1 2 3 4 5 6 7 8 9 10 VERY GOOD
10. Rate the realism of the wind effects.
 BAD 0 1 2 3 4 5 6 7 8 9 10 VERY GOOD
11. Rate the difficulty of the turning maneuver (if applicable).
 LITTLE 0 1 2 3 4 5 6 7 8 9 10 TREMENDOUS

12. Comments:


PILOT RATINGS

INBOUND, FLOOD TIDE




PILOT RATINGS

INBOUND, EBB TIDE




PILOT RATINGS

OUTBOUND, FLOOD TIDE



PILOT RATINGS

OUTBOUND, EBB TIDE



☒ EXIST.
 ☐ PLAN A
 ☒ PLAN B










Plate 22














0 5000 10000 15000
 DISTANCE ALONG TRACK IN FEET
 300/250
 TRANSITION
 TURNING AREA
 FOR EXISTING
 AND PLAN A
 CHANNEL FLARE
 SHIP SPEED AND
 ENGINE RPM
 OUTBOUND, F7B TDE
 LEGEND
 — EXISTING CHANNEL
 PLAN A CHANNEL
 - - - PLAN B CHANNEL
















LEGEND


- BANK LINE
- - - DEEP DRAFT CHANNEL
- - - 20 FT CHANNEL
- - - LESS THAN 16 FT

SCALE IN FEET



PILOT TRACK PLOTS
EXISTING CHANNEL
INBOUND, FLOOD TIDE
ALL PILOTS







LEGEND

- BANK LINE
- DEEP DRAFT CHANNEL
- 20 FT CHANNEL
- LESS THAN 16 FT

SCALE IN FEET



PILOT TRACK PLOTS
PLAN A CHANNEL
INBOUND, FLOOD TIDE
ALL PILOTS






Plate 33B






Plate 34A




LEGEND


- BANK LINE
- DEEP DRAFT CHANNEL
- 20 FT CHANNEL
- LESS THAN 16 FT

SCALE IN FEET



PILOT TRACK PLOTS
EXISTING CHANNEL
INBOUND, EBB TIDE
ALL PILOTS







LEGEND


——— BANK LINE
 - - - - - DEEP DRAFT CHANNEL
 20 FT CHANNEL
 [Hatched Area] LESS THAN 16 FT

SCALE IN FEET



PILOT TRACK PLOTS
PLAN A CHANNEL
INBOUND, EBB TIDE
ALL PILOTS







LEGEND

- BANK LINE
- - - DEEP DRAFT CHANNEL
- - - 20 FT CHANNEL
- - - LESS THAN 16 FT

SCALE IN FEET



PILOT TRACK PLOTS
PLAN B CHANNEL
INBOUND, EBB TIDE
ALL PILOTS







Plate 38







Plate 40







Plate 42






Plate 44

Appendix A

Claremont Channel Ship Simulator Hydrodynamic Study

Introduction

This appendix describes a numerical hydrodynamic model study of the Claremont channel portion of the Upper New York Harbor. This model study was conducted to provide current information necessary to study ship navigation for several channel designs located near the docking facility.

Background

The Claremont channel docking facility is located on the western side of Upper Bay in York Harbor in the state of New Jersey on the borders of Jersey City (Figure A1). A 2-mile (approximately) long access channel connects the facilities at Claremont Terminal to Anchorage Channel, the main shipping lane in New York Harbor (Figure A2). The available navigation channel varies in width at a depth from 25 to 27 ft with a minimum width of 150 ft in some locations from the Claremont Terminal to the intersection with the federally maintained Anchorage Channel. At a nominal depth of 27 ft below mean low water, mlw, the Claremont navigation channel is not deep enough to fully accommodate the dry bulk vessels that export scrap steel and iron from the metropolis of New York. The depth limitation restricts scrap vessels from fully using their available draft. Costly rehandling and topping-off operations at other berths are required to minimize the cost per ton during long ocean voyages.

The typical ship using the port is a Panamax bulk carrier with lengths up to 760 ft, beam of 106 ft, a draft of 16 ft at the bow, 20 ft at the stern in ballast and 30 ft loaded with an even keel. The normal operation involves coming to port in ballast, turn off the end of the Caven Point Pier (also called Ocean Terminal) in the intersections of the Claremont and Pierhead Channels, with the assistance of two 3000 hp tugs, and back into the dock. The ship is loaded to a draft of 30 ft, then the pilot waits for maximum flood tide to transit out.




Figure A2. Claremont channel docking facility location map

This allows a 1.5-ft underkeel clearance (tide range is 4.5 ft). The proposed channel improvements, if implemented, would convert the facility to a federally maintained channel with a draft of 34 ft mlw and width of 300 ft.

Objective

The objective of this hydrodynamic ship simulator study is to evaluate various channel configurations and develop recommendations for a safe and cost-effective channel design. The objective of the hydrodynamic study was to provide current velocity information for ship/tow-simulation (both inbound and outbound).

Scope

This appendix addresses the hydrodynamic model development, validation, and testing.

Technical Approach

The technical approach for the Claremont investigation is described below:

- a. Discuss existing docking procedures with the New York pilots.
- b. Design the Claremont numerical model computational mesh building upon results of previous work performed by CEWES-HL in New York Harbor. In particular, the mesh developed for the Port Jersey (located just south of Claremont) hydrodynamic numerical study was evaluated and improved.
- c. Validate the hydrodynamic model.
- d. Create tidal harmonic boundary conditions.
- e. Run the TABS-MD Claremont hydrodynamic numerical model (RMA2) for the existing channel conditions as defined by the summer 1992 survey of the berthing area.
- f. Incorporate the existing condition predicted velocities at critical stages of the tidal cycle into the ship simulator.
- g. Modify the TABS-MD computational mesh to reflect the NAN channel design (Plan A).
- h. Run the TABS-MD hydrodynamic model (RMA2) for the proposed NAN channel design (Plan A).

- i. Incorporate the Plan A predicted velocities at critical stages of the tidal cycle into the ship simulator.
- j. Modify the TABS-MD computational mesh to reflect the WES proposed channel design (Plan B).
- k. Incorporate the Plan B predicted velocities at critical stages of the tidal cycle into the ship simulator.

Hydrodynamic Numerical Modeling

The TABS-MD Modeling System

The TABS-MD (TABS Multi-Dimensional) numerical modeling system is composed of several finite element models and pre- and post-processing programs. The finite element formulation is isoparametric which allows the mesh to precisely follow the channel alignment and geometry of the pier site. A summary of the TABS-MD system is provided in Appendix B. The RMA2 hydrodynamic model was used to simulate channel velocities and depths under different channel configurations. RMA2 is a time dependent, non-linear, two-dimensional (2D) vertically averaged model for open-channel hydrodynamics. The model solves the depth integrated x- and y-momentum equations along with the continuity equation (Reynolds form of Navier-Stokes equations). FastTABS, an interactive graphical user interface for TABS-MD, was extensively used for this project.

Computational Environment

The Claremont channel hydrodynamic modeling for ship simulation was run on the WES Cray Y-MP super computer during the winter of 1992 through the spring of 1993. The model contained over 13,400 active equations with a front width of 333. Model spin-up was approximately 24 hours. The total simulation was run for 72.0 hours with a maximum of 3 iterations per 15-minute time step. A simulation on the Cray Y-MP required 3 megawords of memory and the typical total central processor time on the loaded computer was 3 hours.

The Computational Meshes

A numerical computational mesh was developed for each bathymetric condition to which RMA2 was applied. For this study there were 3 meshes; existing condition (Base), Plan A, and Plan B. Each of these have the same computational domain, but differ only in the design definition for the Claremont channel width and depth.

The computational domain is shown in Figure A3. The model extends from Troy, NY on the Hudson River, south to the Atlantic Ocean and from the Passaic River at Passaic, NJ, east to Montauk Point on Long Island Sound. The mesh for this study differs from its predecessor Port Jersey study mesh in several ways. The original computational mesh for the Port Jersey study is shown in Figure A4, part a. A subset of the entire Claremont computational mesh is shown in part b of Figure A4 for comparison. Note that the exterior boundaries of the mesh are rounded near the study area in an effort to decrease the boundary break angles and thereby increase the local accuracy in the conservation of mass. This is illustrated by the rounded shape of the ship terminal area. Additional resolution was used throughout. For instance, the constriction along the lower bay at the narrows now has a 13-element cross-section where previously the cross-section had only 6-elements. In addition, the exterior boundaries were moved far from the primary study area to eliminate any boundary sensitivity effects from the results. This was economically accomplished with a one element wide, flat river bottom profile for the extended river boundary regions of Arthur Kill, Passaic River, Hackensack River, and upper Hudson River.

The geometry for the primary Claremont study area was derived from the summer of 1992 survey conducted under the guidance of the New York District. All coordinates were converted with the North American Datum Conversion (NADCON) program developed by the National Geodetic Survey, to reference the Long Island coordinate system. The following National Ocean Service/National Oceanic and Atmospheric Administration (NOAA) nautical charts were used extensively:

Chart No.	Location	Scale	Date
274	Harlem River	1:10000	1951
284	Albany to Troy	1:40000	1969
13205	Block Island Sound	1:80000	1983
12327	New York Harbor	1:40000	1982
12333	Kill van Kull & N. Arthur Kill	1:15000	1982
12335	Hudson and East Rivers	1:10000	1980
12339	Tallman Isl to Queensboro Bridge	1:10000	1984
12343	Hudson R., New York to Wappinger Creek	1:40000	1984
12345	Hudson R., George Washington Bridge	1:10000	1983
12346	Hudson River, Yonkers to Piermont	1:10000	1979
12347	Hudson R., Wappinger Creek to Hudson	1:40000	1985
12354	Eastern part of Long Isl Sound	1:80000	1985
12363	Long Isl Sound, Western part	1:80000	1985




Figure A3. Outline of computational mesh domain




Figure A4. Comparison of the Claremont mesh and the predecessor Port Jersey mesh

All bathymetric data referenced mlw and were converted to an elevation with an arbitrary datum plane of 200 feet. The bathymetry for the model ranges from 6.0 ft deep in the shallows of New York Harbor to 164 ft deep in Long Island Sound. All parts of the computational domain remain submerged during the period of simulation.

Existing Condition - Base. The existing condition (Base), Mesh 1, has 2712 elements and 8656 nodes. Figure A5 shows an enlarged view of the mesh from The Narrows to the Battery. Figure A6 illustrates the resolution for the existing Claremont channel. Approximately 600 elements define the primary study area. The dark shaded area is the Claremont terminal area, the light gray is the pier channel that intersects the primary Claremont channel. Figure A7 is a gray scale shaded map of the bathymetry as defined by the summer 1992 survey conducted under contract by the New York District. The bathymetric readings reference an arbitrary datum of 200 ft. The average element size within the Claremont channel is approximately 190 ft longitudinally and 165 laterally, or 31,350 sq ft. The Claremont channel tracking area was resolved to allow for approximately 2 to 3 elements per ship length, and 1 element per ship width. The existing primary Claremont channel is privately maintained at approximately 27 ft deep at mlw and 150 ft wide.

Proposed Design (Plan A). Mesh 2 represents the channel design proposed in the Claremont Terminal Channel Feasibility Report, Sept 1986. Mesh 2 has 2709 elements and 8667 nodes. Figure A8 illustrates the mesh with proposed changes in the channel design. As shown in the depth contours of Figure A9, Plan A has the channel deepened to 34 ft and widened to 300 ft. For reference, the pier channel is outlined.

Proposed Design (Plan B). Mesh 3 has 2712 elements and 8656 nodes. Figure A10 illustrates the mesh with the WES proposed changes in the channel design. As shown in the depth contours of Figure A11, Plan B has the channel deepened to 34 ft but narrows from 300 ft wide to 250 ft wide at the tip of the Ocean Terminal Pier. For reference, the pier channel is outlined. Note that the southern edge of the primary Claremont channel did not change, only the northern edge was moved to reflect the narrowing.

Hydrodynamic Validation

The rigorous verification of a numerical model requires extensive synoptic field data stations strategically located throughout the modeling domain. Moored water surface elevation gages and velocity meters are usually employed to sample for a non-aliasing data set over several months. These data provide the necessary input for calculating harmonic constituents for the tidal boundary condition and interior verification stations. A detailed velocity profile data set within the primary area of interest for a full tidal cycle is needed also. These data are used to compare numerical model predictions with the prototype. The data collection process can be expensive, and involves




Figure A5. Computational mesh from lower bay to the Battery

careful logistics. However, it remains the primary method of illustrating that the model predicts the behavior of the prototype condition.

Time and budget constraints dictated that a less rigorous method be employed to validate the numerical model. There have been successful TABS-MD hydrodynamics generated for ship simulator applications which did not have large data sets from the prototype. For example the hydrodynamics for the Valdez Alaska project was validated on the basis of NOAA predicted tide tables, pilot interview, and engineering judgement. The hydrodynamics for the ship simulation of Humboldt Bay was validated on the basis of harmonic tides from the TIDE1 Rise and Fall¹ (tide prediction software for the PC) and pilot

¹ TIDE1 Rise and Fall, tide prediction software for the IBM PC, Micronautics, Inc., Rockport, Maine (207-236-0610).




Figure A6. Claremont channel resolution

feedback during simulation with predicted currents. This less rigorous approach was selected for the Claremont hydrodynamic for ship simulation study.




Figure A7. Claremont channel existing (1992) bathymetry

Successful hydrodynamic prediction depends upon on accurate geometric representation and well-posed boundary conditions. In previous numerical model studies of the New York Harbor, boundary conditions were set fairly




Figure A8. Claremont channel, Plan A design




Figure A9. Claremont channel bathymetry, Plan A

close to the study area (Figure A4a) to correspond with the New York Harbor physical model tide and/or velocity stations. An evaluation of the impacts of these close boundary conditions revealed that the model was highly sensitive to minor tidal phase discrepancies and excessive elevation changes at critical sections of the tidal cycle. In an effort to remove discrepancies, the boundary control points were moved far from the study area, as shown in Figures A3 and A12. In addition, predicted tidal harmonic data, obtained from the TIDE1 Rise and Fall software package, were used to ensure accurate phase relationships at the boundaries. Other steps were taken to avoid numerical instability; including a shorter time step, tidal harmonic boundary conditions, gradual exterior boundary break angles, and damping the tidal signal during model spin-up. Furthermore, data obtained from physical model tests were used as general guidelines.

The hydrodynamic validation was accomplished for the base condition, using existing geometry, for a spring tide event. This validation was performed to ensure, within engineering judgement, that the model was responding within required limits of accuracy to:




Figure A10. Claremont channel, Plan B design

- a. Avoid the effects of start up (spin-up).
- b. Achieve numerical stability.
- c. Examine residual currents.
- d. Compare interior stations with tidal harmonics
- e. Observe ship pilots' reaction to predicted currents.

Tidal Boundary Conditions. A spring tidal condition was chosen as a representative challenge for ship maneuverability. The water surface elevations were assigned across the tidal boundaries (Figures A3 and A12). The documented spring tide range are provided in Table A1. As shown in Table 1, the harmonic tidal predictions for the day selected (17 May 92 or Julian day 138) fit the characteristic values for a spring tide event. Figure A13 illustrates how these boundary conditions inter-relate with one another and are all referenced




Figure A11. Claremont channel, Plan B bathymetry




Figure A12. Hydrodynamic boundary control points




Figure A13. Tidal harmonic boundary conditions

to the mean water surface elevation of the model (202.2 ft). Note that the tidal signals were originally damped then gradually amplified to full range within the first 12 hours of the simulation.

Table A1				
Tidal Boundary Conditions				
Location			Documented Spring Tide Range (ft)	17 May 1992 Tide Range (ft)
Station	Latitude	Longitude		
Coney Isl	40° 34' N	73° 59' W	5.7	5.7
Perth Amboy	40° 30' N	74° 16' W	6.3	6.3
Passaic Riv	40° 51' N	74° 07' W	6.2	6.1
Kearney Pt	40° 44' N	74° 06' W	6.1	6.0
Montauk Pt	41° 04' N	71° 52' W	2.5	2.4

Discharge Boundary Condition. The boundary condition for the Hudson River at Troy (location of the head of tide) was a discharge specification. The documented mean river discharge of 6,000 cfs was applied at Troy.

Hydrodynamic Coefficients. User specified coefficients for the hydrodynamic model, RMA2, include Manning's n-value and eddy viscosity. Both were controlled by the element material type (IMAT) descriptor. By grouping elements in IMAT categories, the roughness and viscosity values were easily assigned. Table A2 describes the coefficients for each material type used in the computational mesh. Table A3 provides the actual coefficients used for the hydrodynamic spring tide simulation.

The column marked maximum Peclet # in Table A3 can be used as an indicator of numerical stability. A value of 20 or less is typically recommended for numerical stability. In Table A3, the maximum or "worst case Peclet number" indicates the largest element and the highest velocity within an IMAT group over a tidal cycle. The formula for the Peclet number is given below:

$$P = \frac{u \Delta x (1.94)}{E}$$

where

P = Peclet number

u = streamwise velocity (fps)

Δx = length of the element in the streamwise direction (ft)

E = eddy viscosity (lb-sec/ft²)

1.94 = required for non-SI calculations

Table A2
Element Material Type Assignments

IMAT	Description	Average Length (ft)		Average Area (sq. ft.)
		X	Y	
1	Shallows (less than 15 ft. deep)	800	785	345,401
2	Perimeter of islands	820	950	339,723
3	Dead end zones	1,245	913	593,220
4	Ambrose and Anchorage Channel	1,125	1,435	1,026,923
5	Piers along deep channels	760	1,625	495,301
6	Red Hook and southern East River	900	940	435,693
7	Eastern Kill van Kull approach	995	835	477,956
8	Pier cross channel near Port Jersey	410	412	94,894
9	Port Jersey	615	470	100,408
10	Coney Island Atlantic Ocean Boundary	3,554	4,114	8,706,075
11	Southern Hudson River	1,963	3,722	3,762,872
12	Western Kill van Kull	1,795	1,203	725,990
13	East River near Williamsburg Bridge	1,180	1,118	693,160
14	Upper Hudson River to Troy	3,587	5,553	12,436,735
15	Arthur Kill, Newark Bay, Passaic	2,005	2,140	2,218,114
16	Harlem River	832	1,125	496,308
17	Hellsgate and beginning Long Isl Sound	2,955	3,313	10,672,000
18	Eastern Long Island Sound	14,775	17,565	259,522,875
19	Unused	0	0	0
20	Claremont Ship Channel	270	270	37,723
21	Intersection of Pier Channel & Claremont	357	335	54,601
22	Claremont Terminal general vicinity	207	220	25,300

Residual Currents. Examination of Eulerian residual currents (velocities averaged over a tidal cycle) can provide insight concerning model accuracy. Net effects, such as eddy patterns, can indicate if there is sufficient resolution. Figure A14 illustrates residual vectors obtained from processing hours 37.0 through 49.5 of the RMA2 spring tide simulation (average over a 12.5-hour period). Velocities less than 0.10 fps are plotted as a dot.

Residual Error. Figure A15 illustrates results from a residual error analysis. For the time of maximum ebb, integration of the residual error in the continuity equation reveals that the least error is in the study area where the mesh




Figure A14. Velocities averaged over a 12.5-hour spring tidal cycle




Figure A15. Residual error in the continuity equation of the hydrodynamic model, RMA2


Table A3
Hydrodynamic Coefficient Assignments by zone

Description	Manning's n ft ^{1/3}	Eddy Viscosity (lb-sec/ft ²)	Max Vel fps	Maximum Peclet #
Shallows (less than 15 ft. deep)	0.050	30	0.8	41
Perimeter of islands	0.050	50	1.8	66
Dead end zones	0.020	25	0.6	56
Ambrose and Anchorage Channel	0.020	50	3.2	174
Piers along deep channels	0.030	50	1.4	87
Red Hook and southern East River	0.020	100	4.2	76
Eastern Kill van Kull approach	0.020	50	2.5	92
Pier cross channel near Port Jersey	0.020	15	2.0	106
Port Jersey	0.020	15	0.7	54
Coney Island Atlantic Ocean Boundary	0.020	200	1.8	70
Southern Hudson River	0.020	200	2.6	93
Western Kill van Kull	0.020	150	2.8	54
East River near Williamsburg Bridge	0.020	300	4.3	31
Upper Hudson River to Troy	0.022	500	1.9	37
Arthur Kill, Newark Bay, Passaic	0.022	300	4.4	60
Harlem River	0.022	300	3.3	23
Hellsgate and beginning Long Isl Sound	0.022	1000	7.0	41
Eastern Long Island Sound	0.020	1000	1.5	51
Claremont Ship Channel	0.020	15	0.55	19
Intersection of Pier Channel & Claremont	0.020	15	0.55	16
Claremont Terminal general vicinity	0.020	15	2.0	57


resolution is the highest. As expected, the greatest error (shown in dark shades) is located in the expanded boundary condition regions where the resolution is coarse.

Compare Interior Stations with Tidal Harmonics. Tidal harmonic data are available from published sources (NOAA and TIDE1) for several stations throughout the study area. The data give phase and amplitude variations from station to station. Similar stations were observed in the RMA2 numerical model and compared to the TIDE1 defined relationships. Typical comparisons were made at Fort Hamilton (Figure A16a) which is located near the Narrows, and at the Battery (Figure A16b) which is located between the Hudson and East Rivers. The comparison of defined versus computed water surface elevation is within the accuracy limits required for ship simulation.

CLAREMONT (NY) HARMONIC VERIFICATION, SPRING TIDE



a. Fort Hamilton near the Narrows



b. The Battery located between the Hudson and East Rivers

Figure A16. RMA2 versus harmonic predictions

Maximum Ebb and Flood Velocities. For purposes of ship simulation, the criterion for selecting the time of maximum ebb and flood velocities was a navigable depth of 32 ft or greater at the Claremont ship terminal. The depth averaged velocity results from the RMA2 model at the intersection of the Claremont channel and the Pier channel were compared with the water depth (see Figure A17) and hours 39.25 and 44.00 were selected as the highest velocities with the 32 ft depth criterion. Note that the slight oscillation in velocity magnitude near hours 38.50, 51.0, and 63.0 are the result of cross channel effects. The base condition optimum flood (hour 39.25) and ebb (hour 44.00) velocities in the Claremont and Pier channel intersection are presented in Figures A18 and A19. For reference, Figure A20 illustrates the computed water surface elevation at the Narrows.

Test of Base Versus Plan Channel Designs

Procedures

The plan channel design simulations followed the same basic procedures as outlined for the hydrodynamic model validation. Results from the existing condition geometry with the summer of 1992 bathymetry were compared with the two proposed plan channel designs.

Hydrodynamic Comparisons

Recall that the Claremont channel Plan A design entailed deepening the channel from 30 to 34 ft. Plan B also has the channel deepened to 34 ft but the width narrows from 300 ft to 250 ft wide at the tip of the pier. Since the changes are extremely localized, hydrodynamic changes were found to be confined to the study area.

There are no detectable changes in the water surface elevation between the base condition and either plan A or plan B, see Figure A21.

The changes in velocities within the Claremont and Pier channel intersection were relatively minor. Figures A22 through A24 compare the differences in the x- and y- velocity components and the velocity magnitude between the Base and plans. The influences of the pier channel on the Claremont channel velocities are apparent by the complicated signal. In general, the shallower existing channel had greater velocity extremes than either plan design.

Figures A25 and A26 are the Plan B flood and ebb velocity vector plots. These compare directly with the base Figures A18 and A19 presented earlier. The differences between the plans are not visually detectable.




Figure A17. Velocity and depth for the existing (Base) condition at the Claremont and Pier Channel intersection




Figure A18. Velocity vectors for optimum flood (hour 39.25), existing condition




Figure A19. Velocity vectors for optimum ebb (hour 44.00), existing condition




Figure A20. Water surface elevation at the Narrows, existing condition




Figure A21. Water surface elevation at the Claremont and Pier Channel Intersection, Base versus Plan




Figure A22. X-Component of velocity at the Claremont and Pier Channel Intersection, Base versus Plan




Figure A23. Y-Component of velocity at the Claremont and Pier Channel Intersection, Base versus Plan




Figure A24. Magnitude of velocity at the Claremont and Pier Channel Intersection, Base versus Plan




Figure A25. Velocity vectors for optimum flood (hour 39.25), Plan B




Figure A26. Velocity vectors for optimum ebb (hour 44.00), Plan B

Summary and Conclusions

New insights in numerical model mesh design coupled with a prior knowledge base of the New York Harbor system set the stage for a successful hydrodynamic study to support the tasks of Claremont channel ship simulation. The significant factors are outlined below:

- a. Increased resolution throughout the lower and upper New York Harbor to insure low residual errors within the study area.
- b. Resolved the Claremont channel tracking area to allow for approximately two elements per ship length, and one element per ship width.
- c. Extended the computational domain of the model to provide better boundary condition control points.
- d. Eliminated tidal phasing sensitivity problems by using a 0.25-hr time step and by not using the close boundary condition locations defined by New York Harbor physical model data.
- e. Used tidal harmonic data for all of the boundary conditions except the Hudson River (which used the mean discharge).
- f. Eliminated the problem of tidal reflection by extending the Hudson River to the head of tide at Troy.
- g. Employed new insights and technology in mesh design.
 - (1) Decreased the boundary break angles and thereby increased the local accuracy in the conservation of mass.
 - (2) Used the FastTABS pre- and post-processing interactive graphical tool to check for severe depth gradients, element shape violations, and other errors.

Extending the refined computational domain and using harmonic boundary conditions to drive the two-dimensional vertically integrated RMA2 model proved to be the most critical factors.

Based upon the reactions of the six New York area pilots who used the hydrodynamic data provided by this study for simulation piloting, the study was successful. Furthermore, the project was completed without the added expense of synoptic field data or surveys.

The hydrodynamic differences between the existing conditions and the two plan designs were minor.

Appendix B

The TABS-MD System

TABS-MD is a collection of generalized computer programs and utility codes integrated into a numerical modeling system. TABS-MD is capable of one-, two-, and/or three-dimensional computations; however, only the one- and two-dimensional vertically averaged capability will be discussed in this summary. The system is used for studying hydrodynamics, sedimentation, and transport problems in rivers, reservoirs, bays, and estuaries. A schematic representation of the system is shown in Figure B1. It can be used either as a stand-alone solution technique or as a step in the hybrid modeling approach. The basic concept is to calculate water-surface elevations, current patterns, sediment erosion, transport and deposition, the resulting bed surface elevations, and the feedback to hydraulics. Existing and proposed geometry can be analyzed to determine the impact on sedimentation of project designs and to determine the impact of project designs on salinity and on the stream system. The system is described in detail by Thomas and McAnally (1985).

The three basic 2-D depth-averaged components of the system are as follows:

- a. "A Two-Dimensional Model for Free Surface Flows," RMA2.
- b. "Sediment Transport in Unsteady 2-Dimensional Flows, Horizontal Plane," STUDH.
- c. "Two-Dimensional Finite Element Program for Water Quality," RMA4.

RMA2 is a finite element solution of the Reynolds form of the Navier-Stokes equations for turbulent flows. Friction is calculated with Manning's equation and eddy viscosity coefficients are used to define the turbulent exchanges. A velocity form of the basic equation is used with side boundaries treated as either slip or static. The model has a marsh porosity option as well as the ability to automatically perform wetting and drying. Boundary conditions may be water-surface elevations, velocities, discharges, or tidal radiation.




Figure B1. TABS-MD schematic

The sedimentation model, STUDH, solves the convection-diffusion equation with bed source-sink terms. These terms are structured for either sand or cohesive sediments. The Ackers-White (1973) procedure is used to calculate a sediment transport potential for the sands from which the actual transport is calculated based on availability. Clay erosion is based on work by Partheniades (1962) and Ariathurai and the deposition of clay utilizes Krone's equations (Ariathurai, MacArthur, and Krone 1977). Deposited material forms layers and bookkeeping allows up to 10 layers at each node for maintaining separate material types, deposit thickness, and age. The code uses the same mesh as RMA2.

Salinity calculations, RMA4, are made with a form of the convective-diffusion equation which has general source-sink terms. Up to six conservative substances or substances requiring a decay term can be routed. The code uses the same mesh as RMA2. The model accommodates a mixing zone outside of the model boundaries for estimation of re-entrainment.

Each of these generalized computer codes can be used as a stand-alone program, but to facilitate the preparation of input data and to aid in analyzing results, a family of utility programs was developed for the following purposes:

- a. Digitizing
- b. Mesh generation
- c. Spatial data management
- d. Graphical output
- e. Output analysis
- f. File management
- g. Interfaces
- h. Job control language

Finite Element Modeling

The TABS-MD numerical models used in this effort employ the finite element method to solve the governing equations. To help those who are unfamiliar with the method to better understand the system, a brief description of the method is given here.

The finite element method approximates a solution to governing equations by dividing the area of interest into smaller subareas, which are called elements. The dependent variables (e.g., water-surface elevations and sediment concentrations) are approximated over each element by continuous functions which interpolate based on unknown point (node) values of the variables. An error, defined as the deviation of the governing equations using the approximate solution from the equation using the correct solution, is minimized. Then, when boundary conditions are imposed, a set of solvable simultaneous equations is created. The solution is continuous over the area of interest.


In one-dimensional problems, elements are line segments. In two-dimensional problems, the elements are polygons, usually either triangles or quadrilaterals. Nodes are located on the edges of elements and occasionally inside the elements. The interpolating functions may be linear or higher order polynomials. Figure B2 illustrates a quadrilateral element with eight nodes and a linear solution surface where F is the interpolating function.

Most water resource applications of the finite element method use the Galerkin method of weighted residuals to minimize error. In this method the residual, the local error in the equations use of the approximate and solution, is weighted by a function that is identical to the interpolating function and then minimized. Minimization results in a set of simultaneous equations in terms of nodal values of the dependent variable (e.g. water- surface elevations or sediment concentration). The time portion of time-dependent problems can be solved by the finite element method, but it is generally more efficient to express derivatives with respect to time in finite difference form.


The Hydrodynamic Model, RMA2

Applications

This program is designed for far-field problems in which vertical accelerations are negligible and the velocity vectors at a node generally point in the same directions over the entire depth of the water column at any instant of time. It expects a vertically homogeneous fluid with a free surface. The model will define the response to a specified horizontally inhomogeneous fluid. Both steady and unsteady state problems can be analyzed. A surface wind stress can be imposed and the effects to the earth's rotation can be included.



a. Eight nodes define each element



b. Linear interpolation function

Figure B2. Two-dimensional finite element mesh

The program has been applied to calculate water levels and flow distribution around islands; flow at bridges having one or more relief openings, in contracting and expanding reaches, into and out of off-channel hydropower plants, at river junctions, and into and out of pumping plant channels; circulation and transport in waterbodies with wetlands; and general water levels and flow patterns in rivers, reservoirs, and estuaries.

Limitations

This program is not designed for near-field problems where flowstructure interactions (such as vortices, vibrations, or vertical accelerations) are of interest. Areas of vertically stratified flow are beyond this program's capability unless it is used in a hybrid modeling approach. It is two-dimensional in the horizontal plane, and zones where the bottom current is in a different direction from the surface current must be analyzed with considerable subjective judgment. It is a free-surface calculation for subcritical flow problems.

Governing equations

The generalized computer program RMA2 solves the depth-integrated equations of fluid mass and momentum conservation in two horizontal directions. The form of the solved equations is

$$\begin{aligned}
 h \frac{\partial u}{\partial t} + hu \frac{\partial u}{\partial x} + hv \frac{\partial u}{\partial y} - \frac{h}{\rho} \left(\epsilon_{xx} \frac{\partial^2 u}{\partial x^2} + \epsilon_{xy} \frac{\partial^2 u}{\partial y^2} \right) \\
 + gh \left(\frac{\partial a}{\partial x} + \frac{\partial h}{\partial x} \right) + \frac{g u n^2}{(1.486 h^{1/6})^2} (u^2 + v^2)^{1/2} \\
 - \zeta V_a^2 \cos \psi - 2h\omega v \sin \phi = 0
 \end{aligned} \tag{B1}$$

$$\begin{aligned}
 h \frac{\partial v}{\partial t} + hu \frac{\partial v}{\partial x} + hv \frac{\partial v}{\partial y} - \frac{h}{\rho} \left(\epsilon_{yx} \frac{\partial^2 v}{\partial x^2} + \epsilon_{yy} \frac{\partial^2 v}{\partial y^2} \right) \\
 + gh \left(\frac{\partial a}{\partial y} + \frac{\partial h}{\partial y} \right) + \frac{g v n^2}{(1.486 h^{1/6})^2} (u^2 + v^2)^{1/2} \\
 - \zeta V_a^2 \sin \psi - 2\omega h u \sin \phi = 0
 \end{aligned} \tag{B2}$$

$$\frac{\partial h}{\partial t} + h \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} \right) + u \frac{\partial h}{\partial x} + v \frac{\partial h}{\partial y} = 0 \tag{B3}$$

where

h = depth
 u, v = velocities in the Cartesian directions
 x, y, t = Cartesian coordinates and time
 ρ = density of fluid
 ϵ = eddy viscosity coefficient, for xx = normal direction on x -axis surface; yy = normal direction on y -axis surface; xy and yx = shear direction on each surface
 g = acceleration due to gravity
 a = elevation of bottom
 n = Manning's n value
1.486 = conversion from SI (metric) to non-SI units
 ζ = empirical wind shear coefficient
 V_a = wind speed
 ψ = wind direction
 ω = rate of earth's angular rotation
 ϕ = local latitude

Equations B1, B2, and B3 are solved by the finite element method using Galerkin weighted residuals. The elements may be one-dimensional lines or two-dimensional quadrilaterals or triangles and may have curved (parabolic) sides. The shape functions are quadratic for velocity and linear for depth. Integration in space is performed by Gaussian integration. Derivatives in time are replaced by a nonlinear finite difference approximation. Variables are assumed to vary over each time interval in the form

$$f(t) = f(0) + at + bt^c \quad t_0 \leq t < t_0 + \Delta t \quad (B4)$$

which is differentiated with respect to time, and cast in finite difference form. Letters a , b , and c are constants. It has been found by experiment that the best value for c is 1.5 (Norton and King 1977).

The solution is fully implicit and the set of simultaneous equations is solved by Newton-Raphson non linear iteration. The computer code executes the solution by means of a front-type solver that assembles a portion of the matrix and solves it before assembling the next portion of the matrix. The front solver's efficiency is largely independent of bandwidth and thus does not require as much care in formation of the computational mesh as do earlier traditional solvers.

The code RMA2 is based on the earlier versions (Norton and King 1977) but differs in several ways. It is formulated in terms of velocity (v) instead of unit discharge (vh), which improves some aspects of the code's behavior; it permits drying and wetting of areas within the grid; it permits specification of turbulent coefficients in directions other than along the x - and z -axes; it accommodates the specifications of hydraulic control structures in the network;

it permits wetlands to be simulated as either totally wet/dry or as gradually changing wetting and it permits input in either English or system international units. For a more complete description, see Appendix F of Thomas and McAnally (1985).

The Sediment Transport Model, STUDH

Applications

STUDH can be applied to clay and/or sand bed sediments where flow velocities can be considered two-dimensional (i.e., the speed and direction can be satisfactorily represented as a depth-averaged velocity). It is useful for both deposition and erosion studies and, to a limited extent, for stream width studies. The program treats two categories of sediment: noncohesive, which is referred to as sand here, and cohesive, which is referred to as clay.

Limitations

Both clay and sand may be analyzed, but the model considers a single, effective grain size for each and treats each separately. Fall velocity must be prescribed along with the water-surface elevations, x-velocity, y-velocity, diffusion coefficients, bed density, critical shear stresses for erosion, erosion rate constants, and critical shear stress for deposition.

The program does not compute water-surface elevations or velocities; therefore these data must be provided. For complicated geometries, the numerical model for hydrodynamic computations, RMA2, is used. However, STUDH can only accept a two-dimensional network.

Governing equations

The generalized computer program STUDH solves the depth-integrated convection-dispersion equation in two horizontal dimensions for a single sediment constituent. For a more complete description, see Appendix G of Thomas and McAnally (1985). The form of the solved equation is

$$\begin{aligned} \frac{\partial C}{\partial t} + u \frac{\partial C}{\partial x} + v \frac{\partial C}{\partial y} = \frac{\partial}{\partial x} \left(D_x \frac{\partial C}{\partial x} \right) \\ + \frac{\partial}{\partial y} \left(D_y \frac{\partial C}{\partial y} \right) + \alpha_1 C + \alpha_2 = 0 \end{aligned} \quad (B5)$$

where

C = concentration of sediment

u = depth-integrated velocity in x-direction
 v = depth-integrated velocity in y-direction
 D_x = dispersion coefficient in x-direction
 D_y = dispersion coefficient in y-direction
 α_1 = coefficient of concentration-dependent source/sink term
 α_2 = coefficient of source/sink term

The source/sink terms in Equation B5 are computed in routines that treat the interaction of the flow and the bed. Separate sections of the code handle computations for clay bed and sand bed problems.

Sand transport

The source/sink terms are evaluated by first computing a potential sand transport capacity for the specified flow conditions, comparing that capacity with the amount of sand actually being transported, and then eroding from or depositing to the bed at a rate that would approach the equilibrium value after sufficient elapsed time.

The potential sand transport capacity in the model is computed by the method of Ackers and White (1973), which uses a transport power (work rate) approach. It has been shown to provide superior results for transport under steady-flow conditions (White, Milli, and Crabbe 1975) and for combined waves and currents (Swart 1976). Flume tests at the US Army Engineer Waterways Experiment Station have shown that the concept is valid for transport by estuarine currents.

The total load transport function of Ackers and White is based upon a dimensionless grain size

$$D_{gr} = D \left[\frac{g(s - 1)}{v^2} \right]^{1/3} \quad (B6)$$

where

D = sediment particle diameter
 s = specific gravity of the sediment
 v = kinematic viscosity of the fluid

and a sediment mobility parameter

$$F_{gr} = \left[\frac{\tau'^{n_t} (1-n)}{\rho g D (s-1)} \right]^{1/2} \quad (B7)$$

where

$$\tau' = \text{total boundary shear stress} = \rho g R S$$

where

R = hydraulic radius

S = slope of water surface

n = a coefficient expressing the relative importance of bed-load and suspended-load transport, given in Equation B9

NOTE:

$n = 1$ for fine sediments

$n = 0$ for coarse sediments

τ = boundary surface shear stress

The surface shear stress is that part of the total shear stress which is due to the rough surface of the bed only, i.e., not including that part due to bed forms and geometry. It therefore corresponds to that shear stress that the flow would exert on a plane bed.

The total sediment transport is (in kg/m^3) expressed as an effective concentration

$$G_P = C_A \left[\frac{F_{gr}}{A} - 1 \right]^m \frac{sD}{h} G \left[\frac{\rho}{\tau} U \right]^n \quad (B8)$$

where U is the average flow speed, and for $1 < D_{gr} \leq 60$

$$n = 1.00 - 0.56 \log D_{gr} \quad (B9)$$

$$A = \frac{0.23}{\sqrt{D_{gr}}} + 0.14 \quad (B10)$$

$$\log C_a = 2.86 \log D_{gr} - (\log D_{gr})^2 - 3.53 \quad (B11)$$

$$m = \frac{9.66}{D_{gr}} + 1.34 \quad (B12)$$

For $D_{gr} < 60$

$$n = 0.00 \quad (B13)$$

$$A = 0.17 \quad (B14)$$

$$C_a = 0.025 \quad (B15)$$

$$m = 1.5 \quad (B16)$$

Note the C_a has units consistent with G_p (kg/m^3 for STUDH).

Equations B6-B16 result in a potential sediment concentration G_p . This value is the depth-averaged concentration of sediment that will occur if an equilibrium transport rate is reached with a nonlimited supply of sediment. The rate of sediment deposition (or erosion) is then computed as

$$R = \frac{G_p - C}{t_c} \quad (B17)$$

where

C = present sediment concentration

t_c = time constant

For deposition, the time constant is

$$t_c = \text{larger of} \left\{ \begin{array}{l} \Delta t \\ \text{or} \\ \frac{C_d h}{v_s} \end{array} \right. \quad (B18)$$

and for erosion it is

$$t_c = \text{larger of } \begin{cases} \Delta t \\ \text{or} \\ \frac{C_e h}{U} \end{cases} \quad (\text{B19})$$

where

- Δt = computational time-step
- C_d = response time coefficient for deposition
- V_s = sediment settling velocity
- C_e = response time coefficient for erosion

The sand bed has a specified initial thickness which limits the amount of erosion to that thickness.

Cohesive sediments transport

Cohesive sediments (usually clays and some silts) are considered to be depositional if the bed shear stress exerted by the flow is less than a critical value τ_d . When that value occurs, the deposition rate is given by Krone's (1962) equation

$$S = \begin{cases} -\frac{2V_s}{h} C \left(1 - \frac{\tau}{\tau_d}\right) & \text{for } C < C_c \\ -\frac{2V_s}{hC_c^{2/3}} C^{5/3} \left(1 - \frac{\tau}{\tau_d}\right) & \text{for } C > C_c \end{cases} \quad (\text{B20})$$

(B21)

where

- S = source term
- V_s = fall velocity of a sediment particle
- h = flow depth
- C = sediment concentration in water column
- τ = bed shear stress
- τ_d = critical shear stress for deposition
- C_c = critical concentration = 300 mg/l

If the bed shear stress is greater than the critical value for particle erosion τ_e , material is removed from the bed. The source term is then computed by Ariathurai's (Ariathurai, MacArthur, and Krone 1977) adaptation of Partheniades' (1962) findings:

$$S = \frac{P}{h} \left(\frac{\tau}{\tau_e} - 1 \right) \text{ for } \tau > \tau_e \quad (\text{B22})$$

where P is the erosion rate constant, unless the shear stress is also greater than the critical value for mass erosion. When this value is exceeded, mass failure of a sediment layer occurs and

$$S = \frac{T_L \rho_L}{h \Delta t} \text{ for } \tau > \tau_s \quad (\text{B23})$$

where

T_L = thickness of the failed layer
 ρ_L = density of the failed layer
 Δt = time interval over which failure occurs
 τ_s = bulk shear strength of the layer

The cohesive sediment bed consists of 1 to 10 layers, each with a distinct density and erosion resistance. The layers consolidate with overburden and time.

Bed shear stress

Bed shear stresses are calculated from the flow speed according to one of four optional equations: the smooth-wall log velocity profile or Manning equation for flows alone; and a smooth bed or rippled bed equation for combined currents and wind waves. Shear stresses are calculated using the shear velocity concept where

$$\tau_b = \rho u_*^2 \quad (\text{B24})$$

where

τ_b = bed shear stress
 u_* = shear velocity

and the shear velocity is calculated by one of four methods:

a. Smooth-wall log velocity profiles

$$\frac{\bar{u}}{u_*} = 5.75 \log \left(3.32 \frac{u_* h}{\nu} \right) \quad (\text{B25})$$

which is applicable to the lower 15 percent of the boundary layer when

$$\frac{u_* h}{\nu} > 30$$

where \bar{u} is the mean flow velocity (resultant of u and v components)

b. The Manning shear stress equation

$$u_* = \frac{(\bar{u}n)\sqrt{g}}{CME (h)^{1/6}} \quad (\text{B26})$$

where CME is a coefficient of 1 for SI (metric) units and 1.486 for non-SI units of measurement.

c. A Jonsson-type equation for surface shear stress (plane beds) caused by waves and currents

$$u_* = \sqrt{\frac{1}{2} \left(\frac{f_w u_{om} + f_c \bar{u}}{u_{om} + \bar{u}} \right) (\bar{u} + u_{om})^2} \quad (\text{B27})$$

where

f_w = shear stress coefficient for waves
 u_{om} = maximum orbital velocity of waves
 f_c = shear stress coefficient for currents

d. A Bijker-type equation for total shear stress caused by waves and current

$$U_* = \sqrt{\frac{1}{2} \int_c \bar{u}^2 + \frac{1}{4} \int_n u_{om}^2} \quad (B28)$$

Solution method

Equation B5 is solved by the finite element method using Galerkin weighted residuals. Like RMA2, which uses the same general solution technique, elements are quadrilateral and may have parabolic sides. Shape functions are quadratic. Integration in space is Gaussian. Time-stepping is performed by a Crank-Nicholson approach with a weighting factor (θ) of 0.66. A front-type solver similar to that in RMA2 is used to solve the simultaneous equations.

The Water Quality Transport Model, RMA4

Applications

The water quality model, RMA4, is designed to simulate the depth-average advection-diffusion process in most water bodies with a free surface. The model is used for investigating the physical processes of migration and mixing of a soluble substance in reservoirs, rivers, bays, estuaries and coastal zones. The model is useful for evaluation of the basic processes or for defining the effectiveness of remedial measures. For complex geometries the model utilizes the depth-averaged hydrodynamics from RMA2.

The water quality model has been applied to define the horizontal salinity distribution; to trace temperature effects from power plants; to calculate residence times of harbors or basins; to optimize the placement of outfalls; to identify potential critical areas for oil spills or other pollutants spread; to evaluate turbidity plume extent; and to monitor other water quality criterion within game and fish habitats.

Limitations

The formulation of RMA4 is limited to one-dimensional (cross-sectionally averaged) and two-dimensional (depth-averaged) situations in which the concentration is fairly well-mixed in the vertical. It will not provide accurate concentrations for stratified situations in which the constituent concentration influences the density of the fluid. In addition, the accuracy of the transport model is dependent on the accuracy of the hydrodynamics (e.g. as supplied from RMA2).

Governing Equations

The CEWES version of RMA4 is a revised version of RMA4 as developed by King (1989). The generalized computer program solves the depth-integrated equations of the transport and mixing process. The form of the equations solved is:

$$h \left(\frac{\partial c}{\partial t} + u \frac{\partial c}{\partial x} + v \frac{\partial c}{\partial y} - \frac{\partial}{\partial x} D_x \frac{\partial c}{\partial x} - \frac{\partial}{\partial y} D_y \frac{\partial c}{\partial y} - \sigma + kc \right) = 0 \quad (\text{B29})$$

where

h = water depth

c = constituent concentration

t = time

u, v = velocity components

D_x, D_y = turbulent mixing coefficients

k = first order decay

σ = source/sink of constituent

Note that the basic governing equation for RMA4 is the same as for the sediment transport model, STUDH. The differences between the two models lies in the source/sink terms.

Equation B29 is solved by the finite element method using Galerkin weighted residuals. As with the hydrodynamic model, RMA2, the transport model RMA4 handles one-dimensional segments or two-dimensional quadrilaterals or triangles with the option for curved sides. Spatial integration of the equations is performed by Gaussian techniques and the temporal variations are handled by nonlinear finite differences, consistent with the method described for RMA2. The frontal solution method is also used in RMA4, as with the other programs in the TABS-MD system, to provide an efficient solution algorithm.

The boundary conditions for RMA4 are specified in several optional ways. The boundary concentration may be specified absolutely at a certain level regardless of the flow direction; the concentration can be specified to be applied only when the water is leaving the model; or a mixing zone may be specified just beyond the model boundary to provide the possibility of reentrainment of constituent into the model that may have crossed the boundary earlier. For a more detailed description of the constituent transport model, RMA4, see King and Rachiele, 1989.

Within the one-dimensional formulation of the model, there is a provision for defining the constituent concentration mixing and transport at control

structures as they may have been specified in RMA2. These allow for either a flow through condition, as for example for a wier type flow, or for a mixing chamber type of flux, which would be appropriate for a navigation lock.

References

- Ackers, P., and White, W. R. 1973. (Nov). "Sediment Transport: New Approach and Analysis," *Journal, Hydraulics Division, American Society of Civil Engineers*, Vol 99, No. HY-11, pp 2041-2060.
- Ariathurai, R., MacArthur, R. D., and Krone, R. C. 1977 (Oct). "Mathematical Model of Estuarial Sediment Transport," Technical Report D-77-12, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS.
- King, Ian P., and Richard Rachiele, 1989. "Program Documentation: RMA4 - A Two Dimensional Water Quality Model; Version 3.0", Resource Management Associates, Lafayette, CA.
- Krone, R. B. 1962. "Flume Studies of Transport of Sediment in Estuarial Shoaling Processes," Final Report, Hydraulics Engineering Research Laboratory, University of California, Berkeley, CA.
- Norton, W. R., and King, I. P. 1977 (Feb). "Operating Instructions for the Computer Program RMA-2V," Resource Management Associates, Lafayette, CA.
- Partheniades, E. 1962. "A Study of Erosion and Deposition of Cohesive Soils in Salt Water," Ph.D. Dissertation, University of California, Berkeley, CA.
- Swart, D. H. 1976 (Sep). "Coastal Sediment Transport, Computation of Longshore Transport," R968, Part 1, Delft Hydraulics Laboratory, The Netherlands.
- Thomas, W. A., and McAnally, W. H., Jr. 1985 (Aug). "User's Manual for the Generalized Computer Program System; Open-Channel Flow and Sedimentation, TABS-2, Main Text and Appendices A through O," Instruction Report HL-85-1, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS.
- White, W. R., Milli, H., and Crabbe, A. D. 1975. "Sediment Transport Theories: An Appraisal of Available Methods," Report Int 119, Vols 1 and 2, Hydraulics Research Station, Wallingford, England.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
<small>Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.</small>				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE September 1994		3. REPORT TYPE AND DATES COVERED Final Report
4. TITLE AND SUBTITLE Claremont Terminal Channel, New York Harbor			5. FUNDING NUMBERS	
6. AUTHOR(S) Randy A. McCollum Barbara P. Donnell				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) U.S. Army Engineer Waterways Experiment Station 3909 Halls Ferry Road, Vicksburg, MS 39180-6199			8. PERFORMING ORGANIZATION REPORT NUMBER Technical Report HL-94-14	
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) U.S. Army Engineer District, New York New York, NY 10278-0090			10. SPONSORING / MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES Available from National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161.				
12a. DISTRIBUTION / AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) A ship simulator investigation of Claremont Terminal Channel was performed to determine the effects on ship handling of the proposed widening and deepening of the existing channel from approximately 150 ft to 300 ft and 27 ft mlw to 34 ft mlw, respectively. A hydrodynamic model study of the same area was conducted in support of the ship simulator investigation to supply current fields for the existing channel and proposed channel modifications. This report will describe the ship simulator investigation, its conclusions, and recommendations. Appendix A will describe the hydrodynamic verification and numerical simulation of the existing Claremont Channel bathymetry and two proposed channel design plans. Appendix B describes the governing equations of the TABS-MD numerical modeling system.				
14. SUBJECT TERMS Claremont Channel Numerical hydrodynamic modeling Ship simulation TABS-MD			15. NUMBER OF PAGES 145	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT	